CONTRACT NO. 98950

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	526
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* FAI 57 & FAU 9629 (OLD IL 13)
** (X1-6-2)VB-2, (X1-6)HBK-2

BITUMINOUS PAVEMENT - FAI 57 STAGE 7B

LOCATION STATION TO STATION	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE SUPERPAVE MIX D, N105	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE SUPERPAVE MIX E, N105	POLYMERIZED BITUMINOUS CONCRETE BINDER COURSE SUPERPAVE IL-19.0, N105	BITUMINOUS CONCRETE BINDER COURSE SUPERPAVE IL-19.0, N90 INFO. ONLY		BITUMINOUS CONCRETE PAVEMENT (FULL DEPTH) SUPERPAVE, 14 1/4" FOR INFORMATION ONLY POLY BIT SURFACE MIX D, N105 1 1/2"	POLY BIT BINDER IL-19.0, N105 2 1/4"	BIT BINDER IL-19.0, N90 10 1/2"		STABILIZED SUB-BASE 4"	STABILIZED SUB-BASE (VARIABLE DEPTH)	SUB-BASE GRANULAR MATERIAL, 6"	SUB-BASE GRANULAR MATERIAL, 10"	SUB-BASE GRANULAR MATERIAL, TYPE C	BITUMINOUS MATERIAL (PRIME COAT)	AGGREGATE (PRIME COAT)	MATERIAL TRANSFER DEVICE
	TON	TON	TON	THICKNESS (IN.)	TON	TON	TON	TON	SQ YD	SQ YD	TON	SQ YD	SQ YD	TON	GALLON	TON	TON
FAI 57																	
NORTHBOUND																	
STA 1506+24 TO STA 1506+90			14.0														
STA 1506+90 TO STA 1509+70			106.0														
STA 1509+70 TO STA 1513+00		96.0															
STA 1538+50 TO STA 1542+78			92.0														
SOUTHBOUND																	
STA 1506+71 TO STA 1507+18			16.0														
STA 1507+18 TO STA 1510+30			295.0														
STA 1536+00 TO STA 1542+33			204.0														
STA 1542+33 TO STA 1542+78			12.0														
FAI 57 STAGE 7B PROJECT TOTALS	0	96	739		0				0	0	0	0	0	0	0	0	0

SURFACE REMOVAL - FAI 57 STAGE 7B

LOCATION STA TO STA	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	BITUMINOUS SURFACE REMOVAL 5"	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	TEMPORARY RAMP	REMARKS
	SQ YD	SQ YD	SQ YD	SQ YD	
FAI 57					
NORTHBOUND					
STA 1506+2	70.0				
STA 1513+0	120.0			42.0	
STA 1538+5	63.0			19.0	
STA 1542+7	55.0				
SOUTHBOUND					
STA 1506+71	109.0				
STA 1510+30	148.0			49.0	
STA 1536+00	92.0			34.0	
STA 1542+78	78.0				
FAI 57 STAGE 7B PROJECT TOTAL	735.0	0.0	0.0	144.0	

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE

SCALE: VERT. HORIZ.
DATE
DRAWN BY JCK
CHECKED BY

PLOT DATE = 10/26/2006
FILE NAME = c:\projects\d902802\old13\old13sch.m32
PLOT SCALE = 50.0000 ' / IN.
USER NAME = kranzjo