

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	543
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

### CONCRETE BARRIER - FAI 57 STAGE 7C

LOCATION STATION TO STATION	CONCRETE BARRIER, DOUBLE FACE 42 INCH HEIGHT	TEMPORARY CONCRETE BARRIER	RELOCATE TEMPORARY CONCRETE BARRIER	PROTECTIVE COAT	REMARKS
	FOOT	FOOT	FOOT	SQ YD	
<b>FAI 57</b>					
<b>NORTHBOUND</b>					
STA 1506+90 TO STA 1510+48.26 BK	359.0			519	
STA 1506+90 TO STA 1514+32			763		
STA 1510+49.49 AH TO STA 1513+00	251.0			363	
STA 1541+33 TO STA 1542+33	100.0			111	
STA 1541+33 TO STA 1542+69			150		
<b>SOUTHBOUND</b>					
STA 1505+86 TO STA 1513+00			763		
STA 1540+25 TO STA 1542+33			225		
<b>FAI 57 STAGE 7C PROJECT TOTALS</b>					
	710.0	0.0	1,901.0	993.0	

### GUARD RAIL - FAI 57 STAGE 7C

LOCATION STATION TO STATION	CORING FOR GUARDRAIL INSTALLATION	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 1, (FLARED)	STEEL PLATE BEAM GUARD RAIL, TYPE A	TRAFFIC BARRIER TERMINAL, TYPE 2	TRAFFIC BARRIER TERMINAL, TYPE 5	TRAFFIC BARRIER TERMINAL, TYPE 6	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)	GUARDRAIL REMOVAL	TEMPORARY STEEL PLATE BEAM GUARDRAIL, TYPE A	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 5	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 6	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 10	REMARKS
	FOOT	EACH	FOOT	EACH	EACH	EACH	EACH	FOOT	FOOT	EACH	EACH	EACH	
<b>FAI 57</b>													
<b>SOUTHBOUND</b>													
<b>LT (INSIDE SHOULDER)</b>													
STA. 1506+12 TO STA. 1507+18			62.5	1			1						SEE NOTE 1
<b>FAI 57 STAGE 7C PROJECT TOTALS</b>													
	0.0	0	62.5	1	0	0	1	0.0	0	0	0	0	

NOTE: 1.) THE TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED) SHALL USE A FLARE RATE OF 15:1.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SCHEDULE**

SCALE: VERT. \_\_\_\_\_  
 HORIZ. \_\_\_\_\_  
 DATE \_\_\_\_\_

DRAWN BY JCK  
 CHECKED BY \_\_\_\_\_

PLOT DATE = 12/15/2006  
 FILE NAME = c:\work\projects\982892\old\3\old3\sch.w32  
 PLOT SCALE = 1/8"=1'-0" / IN.  
 USER NAME = kronz.jp