CONTRACT NO. 98950

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	593
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* FAI 57 & FAU 9629 (OLD IL 13)
** (X1-6-2)VB-2, (X1-6)HBK-2

SURFACE REMOVAL - FAI 57 STAGE 8

LOCATION STA TO STA	BITUMINOUS SURFACE REMOVAL - BUTT JOINT SQ YD	BITUMINOUS SURFACE REMOVAL 5" SQ YD	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH) SQ YD	TEMPORARY RAMP SQ YD	REMARKS
FAI 57					
NORTH BOUND					
STA 1505+94	164.0			55.0	
STA 1515+63	83.0			83.0	
STA 1517+56	83.0			83.0	
STA 1517+57 TO STA 1519+5			272.0		
STA 1528+80	93.0			93.0	
STA 1531+14	81.0			81.0	
STA 1543+08	150.0			50.0	
SOUTHBOUND					
STA 1506+41	207.0			69.0	
STA 1515+61	81.0			81.0	
STA 1517+54	91.0			91.0	
STA 1517+99 TO STA 1519+90			235.0		
STA 1526+60 TO STA 1528+78			287.0		
STA 1528+78	83.0			83.0	
STA 1531+12	82.0			82.0	
STA 1543+08	170.0			57.0	
RAMP F					
STA 2+70 TO STA 4+40			439.0		
STA 5+00	87.0			29.0	
RAMP FF					
STA 8+00 TO STA 9+97			509.0		
RAMP E					
STA 12+69 TO STA 14+72			537.0		
RAMP EE					
STA 6+60 TO STA 8+90			240.0		
STA 8+97	93.0			31.0	
FAI 57 STAGE 8 PROJECT TOTAL	1,548.0	0.0	2,519.0	968.0	

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE

SCALE: VERT. HORIZ.
DATE
DRAWN BY JCK
CHECKED BY

PLOT DATE = 10/26/2006
FILE NAME = c:\projects\d902802\old13\old13sch.m32
PLOT SCALE = 50.0000 ' / IN.
USER NAME = kranzjc