

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	**	WILLIAMSON	917	598
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT			

- FAI 57 & FAU 9629 (OLD IL 13)
- (X1-6-2)WB-2, (X1-6)HBK-2

### TEMPORARY PAVEMENT MARKINGS - FAI 57 STAGE 8

LOCATION STATION TO STATION	PAVEMENT MARKING TAPE, TYPE I I I (SPECIAL)			TEMPORARY PAINT PAVEMENT MARKING											SHORT TERM PAVEMENT MARKING	
	LINE 4"			LINE 4"		LINE 6"	LINE 8"		LINE 12"		LINE 24"	LETTERS AND SYMBOLS SQ FT	WHITE FOOT	YELLOW FOOT		
	SKIP-DASH WHITE FOOT	SOLID WHITE FOOT	SOLID YELLOW FOOT	SKIP-DASH WHITE FOOT	SOLID WHITE FOOT	SKIP-DASH YELLOW FOOT	SOLID YELLOW FOOT	SOLID WHITE FOOT	SOLID WHITE FOOT	SOLID YELLOW FOOT	SOLID WHITE FOOT				SOLID YELLOW FOOT	
<b>FAI 57 NORTHBOUND</b>																
STA. 1505+94 TO STA. 1509+63															36	32
STA. 1506+90 TO STA. 1509+63				70			273		196							
STA. 1506+90 TO STA. 1512+12										283						
STA. 1509+63 TO STA. 1510+48.26 BK				20			86								8	8
STA. 1510+49.48 AH TO STA. 1511+69				30		120									12	8
STA. 1511+69 TO STA. 1515+63				100			394									
STA. 1511+69 TO STA. 1519+05															144	56
STA. 1515+63 TO STA. 1516+69		30			106											
STA. 1516+69 TO STA. 1517+56		20			87											
STA. 1517+56 TO STA. 1528+26				270		1,070		1,070								
STA. 1519+05 TO STA. 1526+50															76	56
STA. 1526+50 TO STA. 1528+26															32	16
STA. 1528+26 TO STA. 1528+80										54						
STA. 1528+26 TO STA. 1528+80							54								68	56
STA. 1528+80 TO STA. 1531+14	60		468		234											
STA. 1531+14 TO STA. 1531+86										72						
STA. 1531+14 TO STA. 1534+86				100			372									
STA. 1534+86 TO STA. 1543+00				210		814		814								
STA. 1534+86 TO STA. 1543+08															84	64
<b>SOUTHBOUND</b>																
STA. 1500+00 TO STA. 1507+34				190		305		734		429					64	24
STA. 1506+41 TO STA. 1509+43.5 BK																
STA. 1507+34 TO STA. 1509+43.5 BK				60				210		116						
STA. 1508+10 TO STA. 1513+09				130												
STA. 1509+15.58 AH TO STA. 1510+85				50				170							32	16
STA. 1510+00 TO STA. 1510+85							85									
STA. 1510+85 TO STA. 1514+85				100		400		400		176					80	32
STA. 1514+85 TO STA. 1515+57				40				72		72					16	8
STA. 1515+57 TO STA. 1515+61								4		4					80	32
STA. 1515+61 TO STA. 1517+54	50		386		193											
STA. 1517+54 TO STA. 1519+39				50				185		185						
STA. 1517+54 TO STA. 1523+50												213				
STA. 1518+00 TO STA. 1519+39							139									
STA. 1519+39 TO STA. 1523+50							411									
STA. 1519+39 TO STA. 1527+10															76	64
STA. 1519+39 TO STA. 1528+78																
STA. 1528+78 TO STA. 1529+50		20		72		72										
STA. 1529+50 TO STA. 1531+12		40				162										
STA. 1527+10 TO STA. 1543+08															320	128
STA. 1531+12 TO STA. 1555+97						630				2,485						
<b>RAMP E</b>																
STA. 0+34 TO STA. 0+87.5							277		14		63					
STA. 0+68 TO STA. 3+34								248		247				18		
STA. 2+99 TO STA. 6+60																
STA. 3+34 TO STA. 13+27								993		993						
STA. 13+27 TO STA. 14+73								146					146			
STA. 14+73 TO STA. 15+66																
STA. 15+66 TO STA. 16+65		30			279											
STA. 16+65 TO STA. 20+59.99					99											
STA. 16+65 TO STA. 20+59.99				100		395										

1 OF 2

PLOT DATE = 1/16/2007  
 FILE NAME = c:\pcc\jck\9822802\ad13\ad13sh.m32  
 PLOT SCALE = 50.0000 / IN.  
 USER NAME = jckrj

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
SCALE: VERT.	DRAWN BY JCK	CHECKED BY
DATE		

**SCHEDULE**