

F.A. RILEY	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	**	WILLIAMSON	917	601
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

- FAI 57 & FAU 9629 (OLD IL 13)
- 0X1-6-21VB-2, 0X1-6HKB-2

GUARD RAIL - FAI 57 STAGE 8

LOCATION STATION TO STATION	CORING FOR GUARDRAIL INSTALLATION	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 1, (FLARED) EACH	STEEL PLATE BEAM GUARD RAIL, TYPE A FOOT	TRAFFIC BARRIER TERMINAL, TYPE 2 EACH	TRAFFIC BARRIER TERMINAL, TYPE 5 EACH	TRAFFIC BARRIER TERMINAL, TYPE 6 EACH	TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (FLARED) EACH	GUARDRAIL REMOVAL FOOT	TEMPORARY STEEL PLATE BEAM GUARDRAIL, TYPE A FOOT	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 5 EACH	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 6 EACH	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 10 EACH	REMARKS
	FOOT	EACH	FOOT	EACH	EACH	EACH	FOOT	FOOT	EACH	EACH	EACH		
FAI 57													
NORTHBOUND													
LT (OUTSIDE SHOULDER)													
STA. 1511+62 TO STA. 1514+95	64.0		333.0					333.0					
STA. 1531+14.9 TO STA. 1537+02	95.0		572.0				1	587.0					REMOVE & CONNECT PROPOSED TO TYPE 6 TERM. PLACED IN STAGE 4 - SEE NOTE 2
SOUTHBOUND													
RT (OUTSIDE SHOULDER)													
STA. 1502+24.5 TO STA. 1515+60.4	241.0		1,369.0					1,369.0					REMOVE & CONNECT PROPOSED TO TYPE 6 TERMINAL PLACED IN STAGE 4
RAMP FF													
RT (OUTSIDE SHOULDER)													
STA. 12+39.25 TO STA. 12+45.5				1				31.0					SEE NOTE 1
STA. 14+37.5 TO STA. 16+00								162.5					GUARDRAIL PLACED ON THE SHEET PILING IN STAGE 4
FAI 57 STAGE 8 PROJECT TOTALS													
	400.0	0	2,274.0	1	0	0	1	2,482.5	0	0	0	0	

NOTE: 1.) REMOVAL OF THE TEMPORARY TRAFFIC BARRIER TERMINAL TYPE 6 PLACED IN STAGE 4 AND REPLACE IT WITH A TRAFFIC BARRIER TERMINAL, TYPE 2.
 2.) THE TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED) SHALL USE A FLARE RATE OF 15:1.

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION	
NAME	DATE	SCHEDULE	
		SCALE: VERT. / HORIZ. / DATE	
		DRAWN BY JCK / CHECKED BY	