CONTRACT NO. 98335

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
331	*	WILLIAMSON	8	6
STA. _____ TO STA. _____				
FED. ROAD DIST. NO. _	ILLINOIS	FED. AID PROJECT		

*D9_PAVEMENT_PRESERVATION_FY07

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	FAP 331 (IL 13) EASTBOUND LANES RURAL 100% STATE MICROSURFACING WILLIAMSON IOOO QUANTITY
X0325223	FIBER ASPHALT	POUND	39890	39890
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	6818	6818
1 X4480205	MICRO-SURFACING 2 PASS, TYPE 2	SQ YD	75746	75746
67100100	MOBILIZATION	L SUM	1	1.0
~~70100330~~	~~TRAFFIC CONTROL AND PROTECTION, STANDARD 701426~~	~~L SUM~~	~~1~~	~~1.0~~
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	1.0
70300100	SHORT- TERM PAVEMENT MARKING	FOOT	3834	3834
70300210	TEMPORARY PAVEMENT MARKING-LETTERS AND SYMBOLS	SQ FT	109.2	109.2
70300220	TEMPORARY PAVEMENT MARKING-LINE 4"	FOOT	37735	37735
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	13718	13718
* 78000100	THERMOPLASTIC PAVEMENT MARKING-LETTERS AND SYMBOLS	SQ FT	109.2	109.2
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	37735	37735
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	229	229

*SPECIALTY ITEMS

1 Rev. 4-5-07

Rev.

PLOT DATE = 1/23/2007
FILE NAME = c:\pw_work\
PLOT SCALE = 50.0000 ' / in.
USER NAME = xxxxxxx