


STATION	25 LT. OF CENTERLINE				CENTERLINE				25 RT. OF CENTERLINE			
	PROP.	EXIST.	DEPTH	SLOPE	PROP.	EXIST.	DEPTH	PROP.	EXIST.	DEPTH	SLOPE	
05+50	-	619.96	-	-	620.81	620.65	0.16	-	-	-	-	
05+75	620.06	619.89	0.17	1.40%	620.41	620.25	0.16	-	-	-	-	
06+00	619.70	619.61	0.09	1.20%	620.00	619.91	0.09	-	619.70	-	-	
06+25	619.29	619.19	0.10	1.25%	619.60	619.46	0.14	619.28	619.18	0.10	1.30%	
06+50	618.84	618.64	0.20	1.45%	619.20	618.99	0.21	618.84	618.64	0.20	1.45%	
06+75	618.49	618.31	0.17	1.30%	618.81	618.64	0.17	618.46	618.30	0.16	1.40%	
07+00	618.18	618.08	0.10	1.10%	618.45	618.35	0.10	618.14	618.06	0.08	1.25%	
07+25	617.88	617.79	0.09	1.10%	618.15	618.03	0.12	617.80	617.69	0.11	1.40%	
07+50	617.59	617.45	0.14	1.25%	617.90	617.72	0.18	617.53	617.40	0.13	1.50%	
07+75	617.34	617.21	0.13	1.50%	617.71	617.48	0.23	617.34	617.24	0.10	1.50%	
08+00	617.20	617.07	0.13	1.50%	617.57	617.39	0.18	617.20	617.09	0.11	1.50%	
08+25	617.12	617.01	0.11	1.50%	617.49	617.32	0.17	617.12	616.96	0.15	1.50%	
08+50	617.10	616.94	0.15	1.50%	617.47	617.31	0.16	617.10	616.91	0.19	1.50%	
08+75	617.08	616.95	0.13	1.50%	617.45	617.36	0.09	617.08	616.89	0.19	1.50%	
09+00	617.07	616.94	0.13	1.50%	617.44	617.27	0.17	617.07	616.89	0.18	1.50%	
09+25	617.05	616.86	0.18	1.50%	617.42	617.25	0.17	617.05	616.84	0.20	1.50%	
09+50	617.04	616.89	0.14	1.50%	617.41	617.19	0.22	617.04	616.88	0.15	1.50%	
09+75	617.03	616.93	0.10	1.50%	617.40	617.23	0.17	617.03	616.92	0.11	1.50%	
10+00	617.03	616.94	0.09	1.40%	617.38	617.24	0.14	617.01	616.83	0.17	1.50%	
10+25	617.06	616.96	0.10	1.25%	617.37	617.24	0.13	617.00	616.84	0.15	1.50%	
10+50	617.05	616.96	0.09	1.20%	617.35	617.23	0.12	616.98	616.85	0.13	1.50%	
10+75	617.03	616.94	0.09	1.25%	617.34	617.23	0.11	616.97	616.83	0.13	1.50%	
11+00	617.00	616.91	0.09	1.30%	617.32	617.20	0.12	616.95	616.83	0.12	1.50%	
11+25	617.02	616.93	0.09	1.15%	617.31	617.13	0.18	616.94	616.84	0.09	1.50%	
11+50	617.02	616.93	0.09	1.20%	617.32	617.14	0.18	616.95	616.84	0.11	1.50%	
11+75	617.04	616.88	0.16	1.35%	617.38	617.22	0.16	617.01	616.82	0.18	1.50%	
12+00	617.12	616.91	0.21	1.25%	617.43	617.27	0.16	-	-	-	-	
12+75	617.12	617.02	0.10	1.10%	617.39	617.24	0.15	-	-	-	-	
13+00	617.06	616.95	0.11	1.25%	617.37	617.18	0.19	617.00	616.85	0.14	1.50%	
13+25	617.08	616.98	0.10	1.25%	617.39	617.21	0.18	617.02	616.89	0.13	1.50%	
13+50	617.15	617.06	0.09	1.25%	617.46	617.35	0.11	617.09	616.97	0.12	1.50%	
13+75	617.27	617.18	0.09	1.25%	617.58	617.47	0.11	617.21	617.09	0.12	1.50%	
14+00	617.40	617.29	0.11	1.35%	617.74	617.57	0.17	617.39	617.30	0.09	1.40%	
14+25	617.65	617.47	0.18	1.25%	617.96	617.76	0.20	617.64	617.53	0.11	1.30%	
14+50	617.95	617.84	0.11	1.10%	618.22	617.99	0.23	617.92	617.83	0.09	1.20%	
14+75	618.27	618.06	0.21	1.05%	618.53	618.30	0.23	618.36	618.26	0.10	0.70%	
15+00	618.64	618.43	0.21	0.90%	618.86	618.65	0.21	-	-	-	-	
15+25	618.92	618.82	0.10	1.10%	619.19	619.01	0.18	-	-	-	-	
15+50	619.28	619.18	0.10	0.95%	619.52	619.40	0.12	-	-	-	-	
15+75	619.70	619.60	0.10	0.60%	619.85	619.72	0.13	-	-	-	-	
AVG. LEVELING THICK			0.12				0.16			0.13		

NOTE: EXISTING ELEVATION SHOWN IS PAVEMENT ELEVATION AFTER 1.5" PAVEMENT MILLING.

REVISIONS		
NUMBER	BY	DATE



**GREATER KANKAKEE AIRPORT**  
**KANKAKEE, ILLINOIS**  
**REHABILITATE RUNWAY 4/22**  
**TAXIWAY B**  
**CROWN AND GRADE PAVING CHART**  
**ADDITIVE ALTERNATE #1**

© Copyright CMT, Inc.

**CMT**  
 CRAWFORD, MURPHY & TILLY, INC.  
 CONSULTING ENGINEERS  
 License No. 184-000613

DESIGN BY:	CAL
DRAWN BY:	JRO
CHECKED BY:	CAL
APPROVED BY:	DLP
DATE:	01/26/07
JOB No:	06075-03
IL PROJECT:	IKK-3660
A.I.P. PROJECT:	3-17-0057-B12
SHEET	14 OF 14 SHEETS