SPEC. ITEM	CODE NO.	ITEM NAME	UNIT	TOTAL QUANTITY	I 80% FED 20% STATE 0004	II 80% FED 20% STATE 0011	III 80% FED 20% STATE 0040	IV 80% FED 20% STATE 0021	V 100% ELGIN 0021	VI 80% FED 20% ELGIN 0021	VII 100% STATE 0004	VIII 80% FED 20% ELGIN 0021
	20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	727	727							
	20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	879	863		16					
	20101000	TEMPORARY FENCE	FOOT	258	258							
	20101100	TREE TRUNK PROTECTION	EACH	6	6							
	20101200	TREE ROOT PRUNING	EACH	6	6							
	20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	8	8							
	20200100	EARTH EXCAVATION	CU YD	149753	149753							
	20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	29933	29933							
	20400800	FURNISHED EXCAVATION	CU YD	13672	13672							
	20800150	TRENCH BACKFILL	CU YD	7726	7726							
*	21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	105,569	105,569							
*	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	55200	55200							
*	21101625	TOPSOIL FURNISH AND PLACE, 6"	SQ YD	33120	33120							
*	21101640	TOPSOIL FURNISH AND PLACE, 10"	SQ YD	2269					2269			
*	21101805	COMPOST FURNISH AND PLACE, 2"	SQ YD	57469	55200				2269			
*	25000210	SEEDING, CLASS 2A	ACRE	6.5	6				0.5			
*	25000310	SEEDING, CLASS 4	ACRE	10.5	10.5							
*	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	1654	1654							
*	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	1654	1654							
*	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	1654	1654							
*	25100115	MULCH, METHOD 2	ACRE	1.5	1				0.5			
*	25100630	EROSION CONTROL BLANKET	SQ YD	177386	177386							

LEGEND

I = ROADWAY
II = BRIDGE
III = RETAINING WALLS
IV = IDOT TRAFFIC SIGNALS (MCLEAN @ US 20 SPUI), LIGHTING ON US 20 & RAMPS, AND SIDEWALK REPLACEMENT
V = LIGHTING ON MCLEAN BLVD AND EVP
VI = NEW SIDEWALK
VII = ROADWAY ITEMS WITH 100% STATE FUNDING
VIII = ELGIN TRAFFIC SIGNALS (SPARTAN DR, FLEETWOOD DR, LILLIAN ST)
IX = TRAFFIC SIGNAL INTERCONNECT