

SEE SHEET 4 FOR DESCRIPTION OF COLUMN HEADINGS.

SPEC. ITEM	CODE NO.	ITEM NAME	UNIT	TOTAL QUANTITY	I	II	III	IV	V	VI	VII	VIII
					80% FED 20% STATE 0004	80% FED 20% STATE 0011	80% FED 20% STATE 0040	80% FED 20% STATE 0021	100% ELGIN 0021	80% FED 20% ELGIN 0021	100% STATE 0004	80% FED 20% ELGIN 0021
	48300515	PORTLAND CEMENT CONCRETE SHOULDERS 10 3/4"	SQ YD	29711	29711							
	50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1		1						
	50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1		1						
	50157300	PROTECTIVE SHIELD	SQ YD	876		876						
	50200100	STRUCTURE EXCAVATION	CU YD	1258		1141	117					
	50300225	CONCRETE STRUCTURES	CU YD	1110.4	8.5	1062.3	39.6					
	50300255	CONCRETE SUPERSTRUCTURE	CU YD	2187		2187						
	50300260	BRIDGE DECK GROOVING	SQ YD	6760		6760						
	50300280	CONCRETE ENCASEMENT	CU YD	31.6		31.6						
	50300285	FORM LINER TEXTURED SURFACE	SQ FT	540		540						
	50300300	PROTECTIVE COAT	SQ YD	8198	30	8146	22					
	50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		1						
	50500505	STUD SHEAR CONNECTORS	EACH	20586		20586						
	50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	771860	40810	726470	4580					
	50800515	BAR SPLICERS	EACH	5081		5081						
	50900105	ALUMINUM RAILING, TYPE L	FOOT	73			73					
	50901760	PIPE HANDRAIL	FOOT	32.5	32.5							
	51100100	SLOPE WALL 4 INCH	SQ YD	897		897						
	51201800	FURNISHING STEEL PILES HP14X73	FOOT	6290		6290						
	51202305	DRIVING PILES	FOOT	6290		6290						
	51203800	TEST PILE STEEL HP14X73	EACH	4		4						
	51204650	PILE SHOES	EACH	218		218						
	51500100	NAME PLATES	EACH	1		1						
	52000110	PREFORMED JOINT STRIP SEAL	FOOT	98		98						
	52100520	ANCHOR BOLTS, 1"	EACH	144		144						
	54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	4	4							

N:\DISK45\60044\60H45\SQUID.DGN, N:\DISK45\60H45\SQUID.DGN, N:\DISK45\60H45\SHEET\DISK45\60H45-SHT-SQUID04.DGN
 12-15-2011, 14:17:00
 BAUZEK\ \\FS-0044\KAWALL.D-TRANS.07\2202-21379-001\CIVIL\CAD\60H45\SHEET\DISK45\60H45-SHT-SQUID04.DGN

FILE NAME =	USER NAME = #USER#	DESIGNED -	REVISED -
#FILE#		DRAWN - KKS	REVISED -
	PLOT SCALE = #SCALE#	CHECKED - DDH	REVISED -
	PLOT DATE = #DATE#	DATE - 12/16/11	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION
 FAP ROUTE 345 / US ROUTE 20

SUMMARY OF QUANTITIES - IV

SCALE: N.T.S. SHEET NO. OF STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
345	BR-R	KANE	794	7
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 60H45	