SPEC. ITEM	CODE NO.	ITEM NAME	UNIT	TOTAL QUANTITY	I 80% FED 20% STATE 0004	II 80% FED 20% STATE 0011	III 80% FED 20% STATE 0040	IV 80% FED 20% STATE 0021	V 100% ELGIN 0021	VI 80% FED 20% ELGIN 0021	VII 100% STATE 0004	VIII 80% FED 20% ELGIN 0021	IX 80% FED, 7% STATE 13% ELGIN 0021
•	81702450	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 10	FOOT	450				450					
•	81800410	AERIAL CABLE, 4-1/C NO. 4 WITH MESSENGER WIRE	FOOT	450				450					
•	82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	94				94					
•	82107300	UNDERPASS LUMINAIRE, 150 WATT, HIGH PRESSURE SODIUM VAPOR,	EACH	4				4					
•	83050810	LIGHT POLE, ALUMINUM, 47.5 FT. M.H., 15 FT. MAST ARM	EACH	93				93					
•	83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	830				830					
•	83800205	BREAKAWAY DEVICE, TRANSFORMER BASE, 15 INCH BOLT CIRCLE	EACH	93				93					
•	84200500	REMOVAL OF LIGHTING UNIT, SALVAGE	EACH	95				95					
•	84200804	REMOVAL OF POLE FOUNDATION	EACH	6				6					
•	84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	6				6					
•	84400405	RELOCATE EXISTING WOOD POLES	EACH	8				8					
•	85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	2								2	
•	86000105	MASTER CONTROLLER (SPECIAL)	EACH	1									1
•	86400100	TRANSCEIVER - FIBER OPTIC	EACH	4				1				3	
•	87100020	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM12F	FOOT	3323									3323
•	87300925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	3245									3245
•	87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	7932				4631				3301	
•	87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	10,982				5984				4998	
•	87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	15,316				8397				6919	
•	87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	3769				1133				2636	
•	87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	16542				9350				7192	
•	87301800	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 4 2 C	FOOT	342				342					
•	87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	103								103	
•	87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	4164				2646				1518	
•	87502440	TRAFFIC SIGNAL POST, GALVANIZED STEEL 10 FT.	EACH	6				5				1	
•	87502480	TRAFFIC SIGNAL POST, GALVANIZED STEEL 14 FT.	EACH	10				8				2	

..\D160H45-BORDER01.DGN,..\D160H45-SQDU01.DGN,..\D160H45-SQDU01.DGN
1-24-2012, 15:07:32 SINGHRKK \\FS-6044\HM\VAULT\D-TRANS.87\2282\21379-001\CIVIL\CAD\60H45\SHEET\D160H45-SHT-SQDUIL.DGN