SPEC. ITEM	CODE NO.	ITEM NAME	UNIT	TOTAL QUANTITY	I 80% FED 20% STATE 0004	II 80% FED 20% STATE 0011	III 80% FED 20% STATE 0040	IV 80% FED 20% STATE 0021	V 100% ELGIN 0021	VI 80% FED 20% ELGIN 0021	VII 100% STATE 0004	VIII 80% FED 20% ELGIN 0021
	X6061005	CONCRETE CURB, TYPE B (SPECIAL)	FOOT	1536	1536							
	X6061100	CONCRETE MEDIAN, TYPE SB (SPECIAL)	SQ FT	10122	10122							
	X6063600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.24	FOOT	2529	2529							
	X6370279	CONCRETE BARRIER, SINGLE FACE, 42 INCH HEIGHT (SPECIAL)	FOOT	1589	1589							
	X6640300	CHAIN LINK FENCE REMOVAL	FOOT	1722	1722							
	X6700410	ENGINEER'S FIELD OFFICE, TYPE A (SPECIAL)	CAL MO	24	24							
	X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1							
	X7030025	WET REFLECTIVE TEMPORARY TAPE, TYPE III - LETTERS AND SYMBOLS	SQ FT	1602	1602							
	X7030030	WET REFLECTIVE TEMPORARY TAPE TYPE III, 4 INCH	FOOT	226349	226349							
	X7030040	WET REFLECTIVE TEMPORARY TAPE TYPE III, 6 INCH	FOOT	2099	2099							
	X7030045	WET REFLECTIVE TEMPORARY TAPE TYPE III, 8 INCH	FOOT	26691	26691							
	X7030050	WET REFLECTIVE TEMPORARY TAPE TYPE III, 12 INCH	FOOT	1383	1383							
	X7030055	WET REFLECTIVE TEMPORARY TAPE TYPE III, 24 INCH	FOOT	602	602							
	X7040650	REMOVE TEMPORARY CONCRETE BARRIER	FOOT	13704	13704							
	X7240300	SIGN REMOVAL	EACH	1	1							
•	X8360120	LIGHT POLE FOUNDATION, SPECIAL	EACH	6				6				
•	X8570226	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	3								3
•	X8570231	FULL-ACTUATED CONTROLLER AND TYPE V CABINET, SPECIAL	EACH	1				1				
•	X0324085	EMERGENCY VEHICLE PRIORITY SYSTEM LINE SENSOR CABLE, NO.20 3/C	FOOT	2578					2578			
•	X8900040	MODIFY TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1								1
	XX003822	STORM SEWER REMOVAL, SPECIAL	FOOT	60	60							
	~~Z0001050~~	~~AGGREGATE SUBGRADE 12"~~	~~SQ YD~~	~~135717~~	~~135717~~							
	Z0007601	BUILDING REMOVAL NO. 1	L SUM	1	1							
	Z0007602	BUILDING REMOVAL NO. 2	L SUM	1	1							
	Z0007603	BUILDING REMOVAL NO. 3	L SUM	1	1							
	Z0007604	BUILDING REMOVAL NO. 4	L SUM	1	1							

SEE SHEET 4 FOR DESCRIPTION OF COLUMN HEADINGS.

FILE NAME = $FILEL$
TENG & ASSOCIATES, INC. ENGINEERS/ARCHITECTS/PLANNERS CHICAGO, ILLINOIS
USER NAME = $USER$
PLOT SCALE = $SCALE$
PLOT DATE = $DATE$
DESIGNED - REVISED -
DRAWN - KKS REVISED -
CHECKED - DDH REVISED -
DATE - 12/16/11 REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION
FAP ROUTE 345 / US ROUTE 20

SUMMARY OF QUANTITIES - XV
SCALE: N.T.S. SHEET NO. OF STA. TO STA.

F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
345	8R-R	KANE	794	18

CONTRACT NO. 60H45
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT
Rev

..\D160H45-BORDER01.DGN, ..\D160H45-SOQU01.DGN, ..\D160H45-SOQU01.DGN
12-15-2011, 14:17:41 BAJZEKKJ \\FS-0044\AM\VAULT\D-TRANS_07\2202\21379-001\CIVIL\CAD\60H45\SHEET\D160H45-SHT-SOQU15.DGN