

CONCRETE PAD			TOTAL	352	SQ YD
LOCATION	AREA SQ FT	SUBTOTALS			
SPUI ISLANDS					
NORTHEAST	1006.8	111.87			
SOUTHEAST	729.16	81.02			
SOUTHWEST	1035.53	115.06			
NORTHWEST	395.05	43.89			

CHAIN LINK FENCE, 4'					TOTAL	3933	FOOT
LOCATION	FROM STA.	TO STA.	SUBTOTALS				
US20 E.B.	77+80.27	90+55.46	1,343				
US20 E.B.	90+55.46	98+16.65	815				
US20 W.B.	105+00.00	120+88.89	1775				

PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH, SPECIAL					TOTAL	101	SQ FT
LOCATION	FROM STA.	TO STA.	RT/LT	SUBTOTALS			
EL Faro Restaurant	850+13.60	850+47.25	LT	101.0			

HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH					TOTAL	3920	SQ YD
LOCATION	FROM STA.	TO STA.	SUBTOTALS				
US 20 E.B.	64+37.00	70+00.00	637				
	59+34.86	70+00.00	710				
US 20 W.B.							
US 20 E. B.	60+00.00	70+00.00	667				
	140+24.00	156+01.87	1,753				
	153+41.34	156+01.87	154				

ISLAND PAVEMENT REMOVAL			TOTAL	149	SQ YD
LOCATION	AREA SQ.FT	SUBTOTALS			
MCLEAN BLVD. & FLEETWOOD DR. S.W. CORNER					
MCLEAN BLVD. & FLEETWOOD DR. N.E. CORNER					
MCLEAN BLVD. N.B. LT STA. 72+72.55	525.00	58			
MCLEAN BLVD & RAMP D N.W. CORNER	213.00	24			
MCLEAN BLVD & RAMP A N.E. CORNER	169.49	19			
	80.40	9			
	355.00	39			

FOUNDATION REMOVAL			TOTAL	3	EACH
LOCATION	STATION	OFFSET	SUBTOTALS		
MCLEAN	78+37.38	42.1 RT	1		
MCLEAN	83+67.38	52.4' LT	1		
MCLEAN	83+67.44	42.5' LT	1		

CONCRETE CURB, TYPE B (SPECIAL)					TOTAL	1536	FOOT
LOCATION	FROM STA.	TO STA.	SUBTOTALS				
MCLEAN BLVD. N.B. LT.	76+85.64	78+33.39	155				
MCLEAN BLVD. N.B. LT.	79+11.98	80+01.56	105				
MCLEAN BLVD. N.B. LT.	80+18.47	80+68.07	50				
MCLEAN BLVD. N.B. LT.	80+92.44	81+22.43	30				
MCLEAN BLVD. N.B. LT.	81+56.49	822+49.33	101				
MCLEAN BLVD. N.B. RT.	78+34.63	78+80.96	43				
MCLEAN BLVD. N.B. RT.	79+10.76	80+80.51	170				
MCLEAN BLVD. N.B. RT.	81+04.47	81+30.16	26				
MCLEAN BLVD. N.B. RT.	81+65.11	82+50.55	123				
LILLIAN ST. E.B. LT.	201+18.34	201+68.11	50				
MCLEAN BLVD.N.B. RT.	76+88.54	77+13.17	25				
MCLEAN BLVD.N.B. RT.	83+34.66	85+29.97	211				
MCLEAN BLVD.N.B. RT.	85+62.01	85+93.92	32				
MCLEAN BLVD.N.B. RT.	86+29.02	86+83.28	54				
MCLEAN BLVD.N.B. RT.	87+18.48	87+25.61	7				
MCLEAN BLVD.N.B. LT.	86+13.23	86+54.19	41				
MCLEAN BLVD.N.B. LT.	86+88.33	88+27.91	140				
MCLEAN BLVD.N.B. LT.	88+60.62	88+74.37	14				
LILLIAN ST. W.B. RT.	201+00.00	201+38.00	38				
Fleetwood LT	306+52.61	306+80.86	28				
Fleetwood LT	307+15.86	308+09.54	94				

CONCRETE MEDIAN, TYPE SB (SPECIAL)					TOTAL	10122	SQ FT
LOCATION	FROM STA.	TO STA.	SUBTOTALS				
MCLEAN BLVD.	62+63.52	64+08.63	871				
MCLEAN BLVD.	65+48.03	67+70.50	1,335				
MCLEAN BLVD.	70+45.24	73+02.82	1,545				
MCLEAN BLVD.	75+93.12	82+20.00	3,679				
MCLEAN BLVD.	83+55.00	84+67.63	676				
LILLIAN ST.	200+60.00	201+89.87	779				
FLEETWOOD DR.	307+31.89	309+38.00	1,237				

COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.24					TOTAL	2529	FOOT
LOCATION	FROM STA.	TO STA.	SUBTOTALS				
US 20 N. EDGE	89+94.36	94+98.67	504				
US 20 N. EDGE	101+66.44	107+38.58	572				
US 20 N. EDGE	111+97.91	126+50.01	1,452				

CONCRETE BARRIER, SINGLE FACE, 42 INCH HEIGHT (SPECIAL)						TOTAL	1589	FOOT
LOCATION	FROM STA.	OFFSET FT	TO STA.	OFFSET FT	SUBTOTALS			
US 20	126+50.00		133+00.00		650			
RAMP C	0+00.00	12.00	3+51.00	12.00	351			
RAMP C	3+51.00	12.00	9+39.38	12.00	588			

SIGN REMOVAL			TOTAL	1	EACH
LOCATION	STA.	OFFSET	SUBTOTALS		
MCLEAN BLVD	84+74.00	48' RT	1.00		

AGGREGATE SURFACE COURSE, TYPE B 4"			TOTAL	3916	SQ YD
LOCATION	SQ FT		SUBTOTALS		
BENEATH US 20 BRIDGE WEST OF MCLEAN	17,452.00		1939		
BENEATH US 20 BRIDGE WEST OF MCLEAN	17,793.00		1977		

CHAIN LINK FENCE REMOVAL						TOTAL	1722	FOOT
LOCATION	STA.	OFFSET	STA.	OFFSET	SUBTOTALS			
US 20 W.B.	105+01.69	-197.18	105+97.90	-146.21	107			
US 20 W.B.	105+97.90	-146.21	109+03.60	-119.87	300			
US 20 W.B.	109+03.60	-119.87	109+19.70	-145.18	30			
US 20 W.B.	109+03.60	-119.87	110+08.15	-106.68	104			
US 20 W.B.	110+08.15	-106.68	110+10.60	-119.82	13			
US 20 W.B.	110+08.15	-106.68	112+13.47	-77.93	204			
US 20 W.B.	112+13.47	-77.93	112+17.39	-117.97	40			
US 20 W.B.	121+98.00	-78.65	122+62.19	-80.00	64			
US 20 W.B.	114+89.15	-75.30	114+80.68	-108.24	34			
US 20 W.B.	116+55.38	-89.56	117+10.51	-105.18	57			
US 20 W.B.	118+36.09	-80.24	118+45.93	-80.03	10			
US 20 W.B.	118+45.93	-80.03	118+43.00	-91.14	11			
US 20 W.B.	118+45.93	-80.03	118+93.08	-80.36	47			
US 20 W.B.	118+93.08	-80.36	118+92.89	-90.61	10			
US 20 W.B.	118+93.08	-80.36	119+37.17	-79.92	44			
US 20 W.B.	119+37.17	-79.92	119+37.03	-90.14	10			
US 20 W.B.	119+37.17	-79.92	119+87.78	-80.00	51			
US 20 W.B.	119+87.78	-80.00	119+87.91	-87.25	7			
US 20 W.B.	119+87.78	-80.00	120+37.52	-75.4	50			
US 20 W.B.	120+37.52	-75.40	120+37.71	-83.63	8			
US 20 W.B.	120+37.52	-75.40	120+88.89	-73.54	51			
US 20 W.B.	120+88.89	-73.54	120+88.91	-80.00	6			
US 20 W.B.	120+88.89	-73.54	121+33.94	-77.78	45			
US 20 W.B.	121+33.94	-77.78	121+33.90	-80.00	2			
MCLEAN BLVD	78+33.58	41.62	78+34.69	56.92	15			
MCLEAN BLVD	79+75.26	-63.23	79+67.36	-168.24	105			
MCLEAN BLVD	73+57.95	37.09	75+02.07	35.93	151			
MCLEAN BLVD	73+65.99	35.51	75+06.15	34.82	142			

FENCE REMOVAL						TOTAL	1343	FOOT
LOCATION	STA.	OFFSET	STA.	OFFSET	SUBTOTALS			
US 20 E.B.	77+80.27	81.6	90+55.46	251.9	1,343			

\D:\01\H45-BORDER\01.DGN ... \D:\01\H45-SCHEDULE\01.DGN
 12-14-2011, 9:58:12
 BAIZEKJ \S-0044\MAIN\VAULT.D - TRANS. 07\2202\21379-001\CIVIL\CON\60H45\SHEET\0160H45-SHT-SCHEDULE.06.DGN

FILE NAME =	USER NAME = #USER#	DESIGNED -	REVISED -
#FILE#		DRAWN - JFS	REVISED -
	PLOT SCALE = #SCALE#	CHECKED - DDH	REVISED -
	PLOT DATE = #DATE#	DATE - 12/16/11	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION
 FAP ROUTE 345 / US ROUTE 20

SCHEDULE OF QUANTITIES - VI

SCALE: N.T.S.	SHEET NO.	OF	STA.	TO STA.
---------------	-----------	----	------	---------

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
345	8R-R	KANE	794	44
CONTRACT NO. 60H45				
FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT				