

STAGING & TRAFFIC CONTROL

COMBINATION CONCRETE CURB AND GUTTER, TYPE B-9.12						TOTAL	122	FOOT
LOCATION	STAGE	FROM STA.	TO STA.	LENGTH FT	SUBTOTALS			
McLEAN BLVD. N.B. RT.	II.1	62+90.00	64+10.00	122.40	122.40			

TEMPORARY CONCRETE BARRIER						TOTAL	18739	FOOT
LOCATION	OFFSET	STA. FROM	STA. TO		SUBTOTALS			
STAGE IA								
U.S. 20	WB/EB	68+51.90	146+68.10		7,816			
U.S. 20	WB RT SIDE	68+99.70	71+87.80		288			
U.S. 20	WB RT SIDE	84+05.30	94+27.90		1,023			
U.S. 20	WB RT SIDE	99+18.50	114+30.80		1,512			
U.S. 20	WB RT SIDE	124+18.70	140+24.00		1,605			
STAGE IC								
U.S. 20	WB RT SIDE	77+50.30	84+05.30		655			
STAGE ID								
U.S. 20	WB LT SIDE	94+73.30	99+18.30		445			
U.S. 20	WB LT SIDE	140+24.00	152+28.00		1,204			
STAGE IIA								
U.S. 20	T/ RAMP B	106+00.00	117+00.00		1,100			
U.S. 20	WB/EB	61+66.00	70+00.00		834			
U.S. 20	WB RT SIDE	69+00.10	77+45.50		845			
U.S. 20	WB RT SIDE	132+96.10	141+74.50		878			
STAGE II.2A								
McLean Blvd	SB (RT)	72+74.70	74+84.70		210			
STAGE II.4A								
McLean Blvd	NB (RT)	72+67.10	75+89.50		322			

RELOCATE TEMPORARY CONCRETE BARRIER						TOTAL	40459	FOOT
LOCATION	OFFSET	STATION FROM	STATION TO		SUBTOTALS			
U.S. 20	WB/EB	64+54.40	68+51.90		398			
U.S. 20	WB/EB	146+68.10	153+32.30		664			
U.S. 20	WB RT SIDE	71+87.80	77+50.30		563			
U.S. 20	WB RT SIDE	119+24.70	124+18.70		494			
U.S. 20	WB RT SIDE	140+24.00	146+88.60		665			
STAGE IC								
U.S. 20	WB RT SIDE	114+30.80	119+24.70		494			
U.S. 20	WB RT SIDE	139+60.80	140+40.60		80			
STAGE ID								
U.S. 20	WB LT SIDE	70+00.00	94+73.30		2,473			
U.S. 20	WB LT SIDE	99+18.30	140+24.00		4,106			
U.S. 20	WB LT SIDE	152+28.00	153+28.90		101			
WINTER SHUTDOWN								
U.S. 20	EB RT SIDE	64+54.40	94+72.90		3,019			
U.S. 20	EB RT SIDE	99+18.50	152+28.10		5,310			
U.S. 20	WB RT SIDE	70+00.00	153+28.80		8,329			
STAGE 2A								
U.S. 20	EB RT SIDE	60+31.30	70+00.00		969			
U.S. 20	EB RT SIDE	78+86.90	79+81.10		94			
U.S. 20	EB RT SIDE	84+49.90	111+29.60		2,680			
U.S. 20	EB RT SIDE	118+66.00	121+58.60		293			
U.S. 20	EB RT SIDE	140+24.00	141+44.00		120			
U.S. 20	WB/EB	70+00.00	146+08.60		7,609			
U.S. 20	WB/EB	152+28.10	153+28.80		101			
U.S. 20	WB RT SIDE	141+74.50	148+10.20		636			
STAGE 2B								
U.S. 20	EB RT SIDE	76+73.20	83+10.50		637			
U.S. 20	EB RT SIDE	116+74.90	122+70.00		595			
STAGE II.4B								
McLean Blvd	NB	72+34.05	72+67.10		33			

REMOVE TEMPORARY CONCRETE BARRIER				TOTAL	13704	FOOT
LOCATION	STA.	STA.		SUBTOTALS		
US20 E.B. (RT)	55+76.00	89+24.76		3,348.76		
US20 E.B. (LT)	78+69.06	84+80.85		611.79		
US20 E.B. (RT)	91+65.95	97+60.42		594.47		
US20 E.B. (LT)	94+72.91	97+51.53		278.62		
US20 E.B. (RT)	99+27.05	108+16.49		889.44		
US20 E.B. (RT)	102+74.77	155+31.50		5,256.73		
US20 CENTERLINE	113+57.87	119+24.70		566.83		
US20 CENTERLINE	140+24.00	153+41.34		1,317.34		
US20 E.B. (LT)	60+20.00	68+60.00		840.00		

IMPACT ATTENUATOR REMOVAL				TOTAL	8	EACH
LOCATION	STATION	OFFSET FT		SUBTOTALS		
US 20	55+68	51 RT		1		
US 20	60+20	12 LT		1		
US 20	68+60	12 RT		1		
US 20	78+60	12 LT		1		
US 20	84+38	12RT		1		
US 20	91+60	68 RT		1		
US 20	94+65	12 RT		1		
US 20	102+67	170 RT		1		

IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3				TOTAL	6	EACH
LOCATION	OFFSET	STATION		SUBTOTALS		
STAGE IIA						
U.S. 20	WB	77+62.00		1		
U.S. 20	WB	148+26.00		1		
U.S. 20	EB	83+10.50		1		
U.S. 20	EB	118+50.00		1		
STAGE II.2A						
McLEAN BLVD	SB(RT)	75+00.00		1		
STAGE II.4A						
McLEAN BLVD	NB(RT)	72+52.00		1		

IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3				TOTAL	7	EACH
LOCATION	STATION			SUBTOTALS		
STAGE IA						
US 20 WB	77+65.00			1		
US 20 WB	114+44.00			1		
US 20	WB	147+00.00		1		
STAGE IC						
US 20 WB	140+55.00			1		
STAGE IIA						
US 20 EB	82+96.00			1		
US 20 EB	118+51.00			1		
STAGE IIB						
US 20 EB	76+58.00			1		

TEMPORARY PAVEMENT						TOTAL	36436	SO YD
LOCATION	OFFSET	STATION FROM	STATION TO	AREA SQ. FT.	SUBTOTALS			
McLEAN BLVD II.1								
McLEAN BLVD.	NB(RT)	58+00.00	64+73.60	12,308.00	1,367.56			
McLEAN BLVD.	NB(ISLAND)	65+02.00	65+28.00	395.50	43.94			
FLEETWOOD DR	MEDIAN	310+50.00	311+65.00	1,493.00	165.89			
McLEAN BLVD.	NB(RT)	65+28.00	72+16.00	15,734.30	1,748.26			
McLEAN BLVD.	NB(RT)	72+29.00	75+94.00	13,135.60	1,459.51			
McLEAN BLVD.	NB(RT)	76+60.00	82+85.00	15,242.13	1,693.57			
McLEAN BLVD.	NB(RT)	83+32.00	88+27.00	11,855.84	1,317.32			
MAIN LN	SOUTH			1,688.00	187.56			
McLEAN BLVD II.2A								
McLEAN BLVD.	SB(RT)	64+25.00	64+75.00	1,679.80	186.64			
McLEAN BLVD.	SB(RT)	71+54.66	71+99.79	434.72	48.30			
McLEAN BLVD.	SB(RT)	72+56.99	73+98.18	822.42	91.38			
McLEAN BLVD.	SB(RT)	74+40.00	75+90.21	1,434.66	159.41			
McLEAN BLVD.	SB(RT)	75+32.64	76+05.19	691.48	76.83			
McLEAN BLVD.	SB(RT)	78+74.98	79+35.02	1,201.91	133.55			
McLEAN BLVD.	SB(RT)	82+95.00	83+55.00	574.00	63.78			
MAIN LN	WB			443.00	49.22			
McLEAN BLVD II.2B								
McLEAN BLVD.	SB(RT)	76+10.99	76+50.52		90.56			
McLEAN BLVD.	SB(RT)	72+01.10	72+43.01		109.58			
McLEAN BLVD II.3A								
McLEAN BLVD.	SB(RT)	62+72.00	64+12.00		93.00			
McLEAN BLVD.	SB(RT)	64+75.00	65+35.00		79.89			
McLEAN BLVD.	SB(RT)	65+52.00	71+40.00		538.00			
McLEAN BLVD.	SB(RT)	72+00.00	72+95.00		60.33			
McLEAN BLVD.	NB(LT)	72+00.00	72+95.00		150.44			
McLEAN BLVD.	NB(LT)	75+74.00	82+06.00		459.11			
McLEAN BLVD.	NB(LT)	82+84.00	82+95.00		58.78			
McLEAN BLVD.	NB(LT)	83+40.00	85+20.00		120.00			
McLEAN BLVD II.3B								
McLEAN BLVD.	SB(RT)	82+95.00	83+40.00		49.22			
LILLIAN	W(RT)	200+70.00	201+39.00		19.56			
LILLIAN	W(RT)	202+31.00	203+40.00		56.89			
LILLIAN	W(RT)	204+03.00	205+13.00		47.00			
McLEAN BLVD II.4A								
McLEAN BLVD.	NB(RT)	64+23.00	64+83.00		61.67			
McLEAN BLVD.	NB(RT)	71+73.00	71+93.00		29.78			
McLEAN BLVD.	NB(RT)	75+36.00	75+64.00		35.56			
LILLIAN	E(RT)	200+65.00	203+55.00		213.11			
US-20 STAGE IA								
TEMP RAMP D		700+30.81	704+54.65		1,037.72			
TEMP RAMP B		01+16.70	06+73.40		1,193.26			
TEMP RAMP A		401+83.06	412+92.07		1,909.90			
US-20		119+24.00	140+24.00		2,068.98			
US 20 WB(RT)		134+53.53	145+36.43		1,554.58			
US-20 STAGE IB								
TEMP RAMP D		700+70.61	701+68.76		244.41			
TEMP RAMP A		412+66.03	412+95.62		554.90			
US-20 STAGE IC								
US 20 WB(RT)		68+81.50	94+98.86		5,491.01			
US-20 WB(RT)		78+50.00	84+50.00		739.92			
TEMP RAMP D		700+47.72	701+34.00		227.79			
US 20 WB(RT)		101+66.25	119+24.70		2,107.32			
RAMP A		35+47.00	38+27.00		454.92			
TEMP RAMP B		500+00.00	506+00.00		1249.595556			
US-20 STAGE ID								
US 20 EB(LT)		101+66.20	119+24.70		1,220.11			
US-20 PRE-STAGE IIA								
US 20 (EB RT)		116+25.00	121+50.00		1,125.57			
US-20 STAGE IIA								
US 20 (EB RT)		71+00.00	78+50.00		998.02			
TEMP RAMP C					2,457.34			
TEMP RAMP B					436.14			
US-20		132+00.00	139+00.00		299.61			

\\NF5-804\A\K\VALU\T.D-TRANS-87\2002-21379-001\CIVIL\LOAD\60H45\SHEET\0160H45-SHT-SCHEDULED7.DGN
 \\NF5-804\A\K\VALU\T.D-TRANS-87\2002-21379-001\CIVIL\LOAD\60H45\SHEET\0160H45-SHT-SCHEDULED7.DGN
 \\NF5-804\A\K\VALU\T.D-TRANS-87\2002-21379-001\CIVIL\LOAD\60H45\SHEET\0160H45-SHT-SCHEDULED7.DGN
 \\NF5-804\A\K\VALU\T.D-TRANS-87\2002-21379-001\CIVIL\LOAD\60H45\SHEET\0160H45-SHT-SCHEDULED7.DGN
 \\NF5-804\A\K\VALU\T.D-TRANS-87\2002-21379-001\CIVIL\LOAD\60H45\SHEET\0160H45-S