Structure No.	Description	Station	Offset	Dir.	Proposed RIM Elev.	North	South	East	West	Pipe ID - Pipe SIZE North	Pipe ID - Pipe SIZE South	Pipe ID - Pipe SIZE East	Pipe ID - Pipe SIZE West	Plan Sheet No.	Inlet Filter	Underdrain Connection	STR TOP
981	CB TA 4 DIA T24F&G	87+34	32.8	RT	828.34	823.90	--	--	--	977 - DIA 12"	--	--	--	272	YES	YES	FLAT
982	CB TA 4 DIA T24F&G	88+86	27.7	RT	828.34	--	823.83	--	--	--	978 - DIA 12"	--	--	272	YES	--	FLAT
987	CB TA 4 DIA T24F&G	78+90	48.9	RT	831.73	--	--	828.17	826.07	--	--	EP - DIA 10"	985 - DIA 12"	271	YES	--	FLAT

TEMPORARY DRAINAGE STRUCTURES

Structure No.	Description	Station	Offset	Dir.	Proposed RIM Elev.	North	South	East	West	Pipe ID - Pipe SIZE North	Pipe ID - Pipe SIZE South	Pipe ID - Pipe SIZE East	Pipe ID - Pipe SIZE West	Plan Sheet No.	Inlet Filter	Underdrain Connection	STR TOP	Will Be Paid For At The Contract Unit Price For:
T101	MAN TA 5 DIA T1F CL	406+38	15.3	LT	836.14	825.36	824.90	--	825.00	101 - DIA 24"	EP - DIA 36"	--	102 - DIA 12"	240	--	--	TAPERED	TEMPORARY MANHOLE
T103	MAN TA 4 DIA T1F CL	408+00	24.3	LT	828.29	825.73	--	825.70	825.70	104 - DIA 12"	--	102 - DIA 12"	103 - DIA 12"	240	--	--	FLAT	TEMPORARY MANHOLE
T104	PRC FLAR END SEC 12	409+44	20.0	LT	--	--	--	827.53	--	--	--	103 - DIA 12"	--	240	--	--	--	TEMPORARY END SECTION
T105	PRC FLAR END SEC 12	408+00	11.1	RT	--	--	825.88	--	--	--	104 - DIA 12"	--	--	240	--	--	--	TEMPORARY END SECTION
T201	MAN TA 5 DIA T1F CL	503+84	19.8	RT	837.59	--	825.97	826.00	825.98	--	EP - DIA 24"	204 - DIA 12"	201 - DIA 12"	241	--	--	TAPERED	TEMPORARY MANHOLE
T202	MAN TA 4 DIA T8G	502+00	16.7	RT	832.17	826.69	--	826.69	--	202 - DIA 12"	--	201 - DIA 12"	--	241	--	--	TAPERED	TEMPORARY MANHOLE
T203	MAN TA 4 DIA T8G	502+00	38.8	LT	829.60	--	826.90	--	826.90	--	202 - DIA 12"	--	203 - DIA 12"	241	--	--	FLAT	TEMPORARY MANHOLE
T204	PRC FLAR END SEC 12	500+56	32.9	LT	--	--	--	827.25	--	--	--	203 - DIA 12"	--	241	--	--	--	TEMPORARY END SECTION
T205	MAN TA 4 DIA T8G	505+00	25.4	RT	836.16	--	--	--	826.56	--	--	--	204 - DIA 12"	241	--	--	TAPERED	TEMPORARY MANHOLE
T301	MAN TA 4 DIA T8G	612+70	7.0	RT	828.08	824.66	824.66	--	824.67	302 - DIA 12"	EP - DIA 15"	--	301 - DIA 12"	242	--	--	FLAT	TEMPORARY MANHOLE
T302	MAN TA 4 DIA T8G	609+50	20.6	RT	827.80	--	--	825.80	--	--	--	301 - DIA 12"	--	242	--	--	FLAT	TEMPORARY MANHOLE
T303	MAN TA 4 DIA T8G	612+50	22.6	LT	826.98	--	824.79	--	--	--	302 - DIA 12"	--	--	242	--	--	FLAT	TEMPORARY MANHOLE
T304	PRC FLAR END SEC 12	604+42	31.2	RT	--	--	--	825.92	--	--	--	304 - DIA 12"	--	242	--	--	--	TEMPORARY END SECTION
T305	PRC FLAR END SEC 12	605+50	36.6	LT	--	--	--	--	827.17	--	--	--	304 - DIA 12"	242	--	--	--	TEMPORARY END SECTION
T701	INLETS TA T23F&G	59+50	48.7	RT	824.39	--	--	--	821.40	--	--	--	700 - DIA 12"	235	YES	--	--	TEMPORARY INLET
T703	INLETS TA T23F&G	60+75	51.4	RT	825.39	--	--	--	822.40	--	--	--	702 - DIA 12"	235	YES	--	--	TEMPORARY INLET
T705	INLETS TA T23F&G	63+30	54.0	RT	825.69	--	--	--	822.70	--	--	--	704 - DIA 12"	235	YES	--	--	TEMPORARY INLET
T707	INLETS TA T23F&G	65+51	56.3	RT	825.72	--	--	--	822.75	--	--	--	706 - DIA 12"	235	YES	--	--	TEMPORARY INLET
T709	INLETS TA T23F&G	67+04	47.9	RT	825.64	--	--	--	822.65	--	--	--	708 - DIA 12"	236	YES	--	--	TEMPORARY INLET
T711	INLETS TA T23F&G	77+52	45.9	RT	830.74	--	--	--	827.80	--	--	--	710 - DIA 12"	236	YES	--	--	TEMPORARY INLET
T713	INLETS TA T23F&G	79+97	44.5	RT	830.56	--	--	--	827.60	--	--	--	712 - DIA 12"	236	YES	--	--	TEMPORARY INLET
T715	INLETS TA T23F&G	81+52	46.0	RT	829.99	--	--	--	827.00	--	--	--	714 - DIA 12"	237	YES	--	--	TEMPORARY INLET
T717	INLETS TA T23F&G	85+17	44.4	RT	828.78	--	--	--	825.80	--	--	--	716 - DIA 12"	237	YES	--	--	TEMPORARY INLET
T719	INLETS TA T23F&G	86+49	39.0	RT	828.38	--	--	--	825.40	--	--	--	718 - DIA 12"	237	YES	--	--	TEMPORARY INLET
T801	INLETS TA T23F&G	200+80	46.3	RT	828.79	825.80	--	--	--	800 - DIA 12"	--	--	--	237	YES	--	--	TEMPORARY INLET
T803	INLETS TA T23F&G	202+25	27.7	RT	829.63	826.65	--	--	--	802 - DIA 12"	--	--	--	237	YES	--	--	TEMPORARY INLET
T805	INLETS TA T23F&G	200+70	39.6	LT	828.85	--	825.87	--	--	--	804 - DIA 12"	--	--	237	YES	--	--	TEMPORARY INLET
T807	INLETS TA T23F&G	202+25	33.1	LT	829.52	--	826.55	--	--	--	806 - DIA 12"	--	--	237	YES	--	--	TEMPORARY INLET

TEMPORARY PIPES

Pipe No.	Description	Size	Length	Slope	Trench Backfill	Plan Sheet No.	FROM Node	• TO Node
T101	STORM SEW CL B 2 24	DIA 24"	11	0.39	16.2	240	EP	T101
T102	STORM SEW CL B 1 12	DIA 12"	158	0.44	67.0	240	T103	T101
T103	STORM SEW CL B 1 12	DIA 12"	142	1.29	0.0	240	T104	T103
T104	STORM SEW CL B 2 12	DIA 12"	33	0.44	0.0	240	T105	T103
T201	STORM SEW CL B 2 12	DIA 12"	178	0.40	205.7	241	T202	T201
T202	STORM SEW CL B 2 12	DIA 12"	51	0.40	14.4	241	T203	T202
T203	STORM SEW CL B 1 12	DIA 12"	142	0.25	16.5	241	T204	T203
T204	STORM SEW CL B 2 12	DIA 12"	112	0.50	166.3	241	T205	T201
T301	STORM SEW CL B 1 12	DIA 12"	319	0.36	43.1	242	T302	T301
T302	STORM SEW CL B 2 12	DIA 12"	32	0.40	0.0	242	T303	T301
T304	STORM SEW CL B 2 12	DIA 12"	125	1.00	7.1	242	T305	T304
T700	STORM SEW CL B 1 12	DIA 12"	7	1.00	2.4	235	T701	ES
T702	STORM SEW CL B 1 12	DIA 12"	11	1.00	3.1	235	T703	ES
T704	STORM SEW CL B 1 12	DIA 12"	11	1.00	1.8	235	T705	ES
T706	STORM SEW CL B 1 12	DIA 12"	13	1.00	3.6	235	T707	ES
T708	STORM SEW CL B 1 12	DIA 12"	10	1.00	1.5	236	T709	ES
T710	STORM SEW CL B 1 12	DIA 12"	6	1.00	0.9	236	T711	ES
T712	STORM SEW CL B 1 12	DIA 12"	15	1.00	2.3	236	T713	ES
T714	STORM SEW CL B 1 12	DIA 12"	16	1.00	2.6	237	T715	ES
T716	STORM SEW CL B 1 12	DIA 12"	15	1.00	2.4	237	T717	ES
T718	STORM SEW CL B 1 12	DIA 12"	9	1.00	1.3	237	T719	ES
T800	STORM SEW CL B 1 12	DIA 12"	24	1.00	3.8	237	T801	ES
T802	STORM SEW CL B 1 12	DIA 12"	4	1.00	0.5	237	T803	ES
T804	STORM SEW CL B 1 12	DIA 12"	19	1.00	2.8	237	T805	ES
T806	STORM SEW CL B 1 12	DIA 12"	12	1.00	1.7	237	T807	ES

NOTE: TEMPORARY STORM SEWERS SHALL BE REMOVED ACCORDING TO SECTION 551 OF THE STANDARD SPECIFICATIONS. THE REMOVAL OF THESE STORM SEWERS SHALL BE PAID FOR AT THE CONTRACT UNIT PRICE FOR STORM SEWER REMOVAL OF THE DIAMETER SPECIFIED.

MANHOLES TO BE ADJUSTED

LOCATION	STA	OFFSET	EXISTING RIM ELEV.	PROPOSED RIM ELEV.
MCLEAN	78+71.87	LT	830.31	831.13
MCLEAN	79+08.58	LT	831.26	832.00
MCLEAN	80+41.10	LT	831.04	831.58
MCLEAN	81+52.26	LT	830.69	831.16
MCLEAN	82+56.54	LT	830.23	830.79
MCLEAN	85+18.02	LT	829.47	829.67
LILLIAN	200+67.00	RT	829.42	829.89
LILLIAN	202+25.83	RT	829.89	830.20

FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)

LOCATION	STA	DIRECTION	EXISTING RIM ELEV.	PROPOSED RIM ELEV.
LILLIAN	204+01.44	RT	830.58	830.78
MCLEAN	86+49.40	LT	828.89	828.82
MCLEAN	88+01.44	LT	828.11	828.10