



NOTES:

1. THE CONTRACTOR SHALL INSTALL LIGHT SHIELD ON THIS LIGHT FIXTURE TO AVOID LIGHT SPILLING TOWARDS THE RESIDENTIAL AREAS. THE LIGHT SHIELD SHALL BE INCLUDED IN THE CONTRACT UNIT PRICE FOR "LUMINAIRE" OF THE LAMP TYPE, MOUNT TYPE, AND WATTAGE SPECIFIED.
2. RESTORATION OF WORK AREA - RESTORATION OF LIGHTING WORK AREA SHALL BE INCIDENTAL TO THE RELATED PAY ITEM SUCH AS FOUNDATION, CONDUITS, HANDHOLE, ETC. AND NO EXTRA COMPENSATION SHALL BE ALLOWED. ALL ROADWAY SURFACES SUCH AS SHOULDERS, MEDIANS, SIDEWALKS, PAVEMENT, ETC. SHALL BE REPLACED IN KIND. ALL DAMAGE TO MOWED LAWNS SHALL BE REPLACED WITH AN APPROVED SOD AND ALL DAMAGE TO UNMOWED FIELD, SHALL BE SODDED OR SEEDED IN ACCORDANCE WITH STANDARD SPECIFICATIONS 252 AND 250 RESPECTIVELY.
3. LIGHT POLE TO BE MOUNTED ON FOUNDATION INTEGRAL WITH SINGLE FACE CONCRETE BARRIER. SEE ROADWAY DETAILS, DRILLED SHAFT FOUNDATIONS FOR LIGHT POLES ALONG SINGLE FACE CONCRETE BARRIERS.
4. SEE RAMP D RETAINING WALL (SN 045-W010) PLANS IN PREVIOUS CONTRACT 60K90.

GO GANDHI AND ASSOCIATES, INC.
ENGINEERS AND PLANNERS
6035 N. NORTHWEST HIGHWAY
SUITE 306
CHICAGO, ILLINOIS 60631 TEL. (773) 774-5900

FILE NAME =	USER NAME = .GAL.
\$FILEL#	
PLOT SCALE = 1"=50'	
PLOT DATE = 12/8/2011	

DESIGNED - PKG	REVISED -
DRAWN - MAA, SHM	REVISED -
CHECKED - PKG	REVISED -
DATE - 12/16/11	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

PROPOSED LIGHTING PLAN (SHEET 1 OF 4)			
SCALE: 1"= 50'	SHEET NO.	OF SHEETS	STA. TO STA.

F.A.P. RTE. 345	SECTION 8R-R	COUNTY KANE	TOTAL SHEETS 794	SHEET NO. 444
CONTRACT NO. 60H45				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				