

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODES								
				ROADWAY IL 38/KAUTZ		BRIDGE SN 045-0079 (PROPOSED)	SAFETY TRAFFIC SIGNALS	SAFETY LIGHTING	WATER MAIN & CASING	CASING PIPE	WATER MAIN & SANITARY	BIKE PATH
				KANE COUNTY	DUPAGE COUNTY	KANE COUNTY	KANE COUNTY	KANE COUNTY	KANE COUNTY	DUPAGE COUNTY	KANE COUNTY	DUPAGE COUNTY
				80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 13.2% STATE 3.4% GENEVA 3.4% WEST CHICAGO	100% STATE	100% GENEVA	100% WEST CHICAGO	80% FED. 20% STATE	80% FED. 20% DUPAGE CTY
81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	4,118	0004	0004	0008	0021	0021	0043	0043	0043	0028
81028210	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2 1/2" DIA.	FOOT	35				35					
81028220	UNDERGROUND CONDUIT, GALVANIZED STEEL, 3" DIA.	FOOT	44				44					
81028240	UNDERGROUND CONDUIT, GALVANIZED STEEL, 4" DIA.	FOOT	1,048				742	306				
81100800	CONDUIT ATTACHED TO STRUCTURE, 3" DIA., GALVANIZED STEEL	FOOT	20				20					
81101000	CONDUIT ATTACHED TO STRUCTURE, 4" DIA., GALVANIZED STEEL	FOOT	320				320					
81300948	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 24" X 24" X 10"	EACH	2				2					
81400100	HANDHOLE	EACH	11				9	2				
81400300	DOUBLE HANDHOLE	EACH	2				2					
81603035	UNIT DUCT, 600V, 2-1C NO.6, 1/C NO.6 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	2,184					2,184				
81702440	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 1/0	FOOT	179					179				
81702130	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6	FOOT	348					348				
81800200	AERIAL CABLE, 2-1/C NO. 4 WITH MESSENGER WIRE	FOOT	958					958				
82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	12					12				
83008500	LIGHT POLE, ALUMINUM, 40 FT. M.H., 12 FT. MAST ARM	EACH	8					8				
83057170	LIGHT POLE, WOOD, 35 FOOT, CLASS 3	EACH	3					3				
83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	100.0					100.0				
83800205	BREAKAWAY DEVICE, TRANSFORMER BASE, 15 INCH BOLT CIRCLE	EACH	8					8				
84100110	REMOVAL OF TEMPORARY LIGHTING UNIT	EACH	7					7				
84200804	REMOVAL OF POLE FOUNDATION	EACH	11					11				
84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	4					4				
84500120	REMOVAL OF ELECTRIC SERVICE INSTALLATION	EACH	1					1				
84500130	REMOVAL OF LIGHTING CONTROLLER FOUNDATION	EACH	1					1				
85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	2				2					
86400100	TRANSCEIVER - FIBER OPTIC	EACH	1				1					
87100020	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SMI2F	FOOT	5,864				5,864					
87300925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	5,864				5,864					
87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	1,481				1,481					
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	2,757				2,757					
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	2,380				2,380					
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	2,426				2,426					
87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	118				118					
87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	1,230				1,230					
87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	2				2					
87700280	STEEL MAST ARM ASSEMBLY AND POLE, 48 FT.	EACH	1				1					

• DENOTES SPECIALTY ITEM
 Δ DENOTES 100% FUNDING BY WEST CHICAGO FIRE PROTECTION DISTRICT

FILE NAME = D160122-SH1-S0006.dgn	USER NAME = EricG	DESIGNED - MJT	REVISED -
		DRAWN - MJT	REVISED -
		CHECKED - EJC	REVISED -
		DATE - 12/09/11	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NONE SHEET NO. 6 OF 9 SHEETS STA. TO STA.

F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
347	LY (HB & VB)	DUPAGE/KANE	421	9
SQ-6		CONTRACT NO. 60122		
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				