

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	SAFETY					CODE NO	ITEM	UNIT	TOTAL QUANTITIES	SAFETY				
				0021									0021				
81603051	UNIT DUCT, 600V, WITH 3-1/2 NO. 6, 1/2 NO. 8 GROUND, (XLP-TYPE USE), 1 1/4" DIA., POLYETHYLENE	FOOT	2692	2692					* 81028220	UNDERGROUND CONDUIT, GALVANIZED STEEL, 3" DIA.	FOOT	208	208				
20200100	EARTH EXCAVATION	CU YD	177	177					* 82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	11	11				
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	307	307					* 83007500	LIGHT POLE, ALUMINUM, 35 FT. M.H., 12 FT. MAST ARM	EACH	11	11				
20400800	FURNISHED EXCAVATION	CU YD	42	42					* 83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	207	207				
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	90	90					* 83800505	BREAKAWAY DEVICE, COUPLING, WITH ALUMINUM SKIRT	EACH	108	108				
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	2	2					* 84200500	REMOVAL OF LIGHTING UNIT, SALVAGE	EACH	2	2				
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	2	2					* 84200804	REMOVAL OF POLE FOUNDATION	EACH	23	23				
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	2	2					* 84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	16	16				
25200110	SODDING, SALT TOLERANT	SO YD	90	90					* 85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1	1				
28000400	PERIMETER EROSION BARRIER	FOOT	550	550					* 87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	250	250				
28000510	INLET FILTERS	EACH	35	35					* 87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	254	254				
42001300	PROTECTIVE COAT	SO YD	4800	4800					* 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	60	60				
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	42400	42400					* 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	60	60				
42400800	DETECTABLE WARNINGS	SO FT	200	200					* 87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	194	194				
44000100	PAVEMENT REMOVAL	SO YD	2700	2700					* 87502440	TRAFFIC SIGNAL POST, GALVANIZED STEEL 10 FT.	EACH	1	1				
44000600	SIDEWALK REMOVAL	SO FT	6775	6775					* 87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	1	1				
* 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	1304	1304					* 87800100	CONCRETE FOUNDATION, TYPE A	FOOT	8	8				
* 66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1					* 88030240	SIGNAL HEAD, LED, 2-FACE, 1-3 SECTION, 1-5 SECTION, BRACKET MOUNTED	EACH	1	1				
* 66900530	SOIL DISPOSAL ANALYSIS	EACH	9	9					* 88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	1	1				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6					* 88102747	PEDESTRIAN SIGNAL HEAD, LED, 2-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	1	1				
67100100	MOBILIZATION	L SUM	1	1					* 88800100	PEDESTRIAN PUSH-BUTTON	EACH	3	3				
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1					* 89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1	1				
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	1					* 89502376	REBUILD EXISTING HANDHOLE	EACH	4	4				
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1					* 89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	1	1				
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1					* X0325924	CLEAN, RELAMP AND MAINTENANCE OF EXISTING LUMINAIRE	EACH	50	50				
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	395	395					Δ X5537800	STORM SEWERS TO BE CLEANED 12"	FOOT	1750	1750				
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	345	345					* X8100863	INTERCEPT EXISTING CONDUIT	EACH	3	3				
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	521	521													
* 78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	205	205													
78300100	PAVEMENT MARKING REMOVAL	SO FT	950	950													
* 81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	37	37													

* SPECIALTY ITEMS
Δ NON-PARTICIPATING ITEMS
(100% STATE)