

SUMMARY OF QUANTITIES

CODED PAY ITEM NUMBER	PAY ITEM	UNIT	TOTAL QUANTITIES	801.FED./201.STATE URBAN CONSTRUCTION TYPE CODE	
				ROADWAY 0004	BRIDGE REPLACEMENT 0011
* 20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	72	72	
* 20101000	TEMPORARY FENCE	FOOT	86	86	
* 20101200	TREE ROOT PRUNING	EACH	5	5	
* 20101300	TREE PRUNING (1 TO 10 INCH DIAMETER)	EACH	5	5	
* 20101700	SUPPLEMENTAL WATERING	UNIT	1	1	
20200100	EARTH EXCAVATION	CU YD	512	512	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	266	266	
20300100	CHANNEL EXCAVATION	CU YD	44	44	
20400800	FURNISHED EXCAVATION	CU YD	62	62	
20700220	POROUS GRANULAR EMBANKMENT	CU YD	7		7
20800150	TRENCH BACKFILL	CU YD	27	27	
* 21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	2514	2514	
* 25000210	SEEDING, CLASS 2A	ACRE	0.25	0.25	
* 25000312	SEEDING, CLASS 4A	ACRE	0.50	0.50	
* 25000314	SEEDING, CLASS 4B	ACRE	0.25	0.25	
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	12	12	
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	12	12	
* 25100115	MULCH, METHOD 2	ACRE	0.75	0.75	
* 25100630	EROSION CONTROL BLANKET	SQ YD	2514	2514	
* 28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	52	52	
* 28000305	TEMPORARY DITCH CHECKS	FOOT	28	28	
* 28000400	PERIMETER EROSION BARRIER	FOOT	804	804	
* 28000510	INLET FILTERS	EACH	3	3	
28100107	STONE RIPRAP, CLASS A4	SQ YD	697		697
28200200	FILTER FABRIC	SQ YD	697		697

* INDICATES SPECIALTY ITEMS

CODED PAY ITEM NUMBER	PAY ITEM	UNIT	TOTAL QUANTITIES	801.FED./201.STATE URBAN CONSTRUCTION TYPE CODE	
				ROADWAY 0004	BRIDGE REPLACEMENT 0011
31101400	SUBBASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	497	497	
35501317	HOT-MIX ASPHALT BASE COURSE, 8 1/4"	SQ YD	680	680	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	469	469	
40600300	AGGREGATE (PRIME COAT)	TON	8	8	
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	131	131	
40600895	CONSTRUCTING TEST STRIP	EACH	1	1	
40603240	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	280	280	
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	227	227	
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	1607	1607	
44000100	PAVEMENT REMOVAL	SQ YD	430	430	
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	1231	1231	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	833	833	
44000600	SIDEWALK REMOVAL	SQ FT	1416	1416	
44003100	MEDIAN REMOVAL	SQ FT	2328	2328	
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1
50104400	CONCRETE HEADWALL REMOVAL	EACH	2	2	
50200100	STRUCTURE EXCAVATION	CU YD	362		362
50300225	CONCRETE STRUCTURES	CU YD	228.5		228.5
50300255	CONCRETE SUPERSTRUCTURE	CU YD	10.5		10.5
50300300	PROTECTIVE COAT	SQ YD	59		59
50800105	REINFORCEMENT BARS	POUND	17300		17300
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	9550		9550
50800515	BAR SPLICERS	EACH	84		84
50900105	ALUMINUM RAILING, TYPE L	FOOT	49		49
51500100	NAME PLATES	EACH	1		1

* INDICATES SPECIALTY ITEMS

FILE NAME = ... \DI6083-sht-5001-PostFinal.dgn



DESIGNED - RJD
DRAWN - GEW
CHECKED - RJD
DATE - 12/12/2011

REVISED -
REVISED -
REVISED -
REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**IL ROUTE 53 OVER ST JOSEPH'S CREEK
SUMMARY OF QUANTITIES**

SCALE: N/A SHEET NO. 1 OF 3 SHEETS STA. TO STA.

F.A.P. RTE. 870	SECTION 534R-B	COUNTY DUPAGE	TOTAL SHEETS 51	SHEET NO. 3
CONTRACT NO. 60M83				
ILLINOIS FED. AID PROJECT				