SIGNING SCHEDULE

SIGN NAME	STATION	SIGN DESCRIPTION	EXISTING PANEL DIMENSIONS WIDTH (FT)	EXISTING PANEL DIMENSIONS HEIGHT (FT)	PROPOSED PANEL DIMENSIONS WIDTH (FT)	PROPOSED PANEL DIMENSIONS HEIGHT (FT)	REMOVE SIGN PANEL - TYPE 1 (SQ FT)	REMOVE SIGN PANEL - TYPE 2 (SQ FT)	REMOVE SIGN PANEL - TYPE 3 (SQ FT)	REMOVE SIGN PANEL ASSEMBLY - TYPE A (EACH)	REMOVE SIGN PANEL ASSEMBLY - TYPE B (SPECIAL) (EACH)	RELOCATE SIGN PANEL - TYPE 1 (SQ FT)	SIGN PANEL - TYPE 1 (SPECIAL) (SQ FT)	SIGN PANEL - TYPE 2 (SPECIAL) (SQ FT)	SIGN PANEL - TYPE 3 (SPECIAL) (SQ FT)	WOOD SIGN SUPPORT (FT)	TELESCOPING STEEL SIGN SUPPORT (FT)	REMOVAL OF LIGHTING UNIT, NO SALVAGE (EACH)	REMOVE OVERHEAD SIGN STRUCTURE - WALKWAY (FOOT)
SWB-WP-1002	80+81	W4-1R -- MERGE	4.0	4.0	4.0	4.0					1			16.0		18			
NEB-WP-1003	83+06	W4-1R -- MERGE	4.0	4.0	4.0	4.0					1			16.0		18			
SWB-WP-1004	84+77	R4-5X -- END TRUCK LANE RESTRICTIONS	4.0	5.0	4.0	5.0					1			20.0		18			
SWB-WP-1005	89+48	E5-1a -- EXIT 5	6.5	5.0	6.5	5.0					1				32.5	36			
SWB-TR-1006A	96+04	GUIDE -- EXIT 7, 355 SOUTH TOLLWAY/JOLIET, 1 1/2 MILES	16.5	14.5	16.5	14.5			239.3						239.3			6	55
SWB-TR-1006B	96+04	GUIDE -- EXIT 5, THORNDALE AVE/TO ELGIN-O'HARE EXPY, EXIT ONLY	26.0	13.5	26.0	13.5			351.0						351.0				
SWB-WP-1007	96+54	W13-3 -- 35 MPH	4.0	5.0	4.0	5.0					1			20.0		18			
NEB-WP-1008	98+92	R4-5X -- NO TRUCKS IN 2 LEFT LANES	4.0	6.0	4.0	6.0					1				24.0	18			
NEB-PM-1009A	100+47	M3-4 -- BLUE BACKGROUND	3.0	1.5	3.0	1.5	4.5						4.5						
NEB-PM-1009B	100+47	M1-1 -- 290	3.8	3.0	3.8	3.0		11.3						11.3					
NEB-BR-1010A	100+86	GUIDE -- BIESTERFIELD RD IL 53 SOUTH 1/2 MILE	20.0	15.0	20.0	15.0			300.0						300.0			3	20
NEB-BR-1010B	100+86	D3-1 -- DEVON AVE	7.0	1.5	7.0	1.5		10.5						10.5					
SWB-BR-1011	101+86	D3-1 -- DEVON AVE	7.0	1.5	7.0	1.5		10.5						10.5					
NEB-PM-1012	104+57	R2-1 -- 55 MPH	4.0	5.0	4.0	5.0		20.0						20.0					
NEB-WP-1015A	107+52	D9-2 -- BLUE BACKGROUND	2.5	2.5	2.5	2.5					1		6.3			18			
NEB-WP-1015B	107+52	SERVICE -- EXIT 4	-	-	2.5	1.3							3.1						
NEB-WP-1016	111+26	REGULATORY -- MOVE OVER-SLOW DOWN	10.0	3.0	10.0	3.0					1				30.0	36			
SWB-WP-1017	111+65	REGULATORY -- MOVE OVER-SLOW DOWN	10.0	3.0	10.0	3.0					1				30.0	36			
SWB-WP-1018	115+57	SERVICE -- SHARE THE DRIVE	10.0	5.0	10.0	5.0					1				50.0	36			
SWB-CL-1019	115+71	GUIDE -- EXIT 5, THORNDALE AVE/TO ELGIN-O'HARE EXPY, EXIT ONLY	25.5	12.0	25.5	12.0			306.0						306.0			3	20
SWB-WP-1020	118+98	R2-1 -- 55 MPH	4.0	5.0	4.0	5.0					1			20.0		18			
NEB-CL-1021A	120+43	GUIDE -- BIESTERFIELD RD IL 53 SOUTH EXIT ONLY	20.0	13.0	20.0	13.0			260.0						260.0			3	25
NEB-PM-1021B	120+43	W13-3 -- 30 MPH	4.0	5.0	4.0	5.0		20.0						20.0					
SWB-WP-1022A	122+27	M3-2 -- BLUE BACKGROUND	3.0	1.5	3.0	1.5					1		4.5			18			
SWB-WP-1022B	122+27	M1-1 -- 290	3.8	3.0	3.8	3.0								11.3					
NEB-WP-1023	126+10	E5-1a -- EXIT 4	6.5	5.0	6.5	5.0					1				32.5	36			
SWB-WP-1026	132+21	W4-3R -- ADDED LANE	4.0	4.0	4.0	4.0					1			16.0		18			
NEB-WP-1027	134+25	W4-3R -- ADDED LANE	4.0	4.0	4.0	4.0					1			16.0		18			
NEB-BR-1028	141+29	D3-1 -- BIESTERFIELD RD	9.5	1.5	9.5	1.5		14.3						14.3					
SWB-BR-1029A	142+70	GUIDE -- EXIT 7, 355 SOUTH TOLLWAY/JOLIET, 2 1/2 MILES	16.0	14.5	16.0	14.5			232.0						232.0			5	42
SWB-BR-1029B	142+70	GUIDE -- EXIT 5, THORNDALE AVE/TO ELGIN-O'HARE EXPY, 1 MILE	26.5	14.5	26.5	14.5			384.3						384.3				
NEB-WP-1030A	147+00	M3-4 -- BLUE BACKGROUND	3.0	1.5	3.0	1.5					1		4.5			18			
NEB-WP-1030B	147+00	M1-1 -- 290	3.8	3.0	3.8	3.0								11.3					
NEB-WP-1030C	147+00	M3-1 -- WHITE BACKGROUND	3.0	1.5	3.0	1.5							4.5						
NEB-WP-1030D	147+00	M1-I100 -- IL 53	3.0	3.0	3.0	3.0							9.0						
SWB-WP-1031	150+08	E5-1a -- EXIT 4	6.5	5.0	6.5	5.0					1				32.5	36			
NEB-WP-1032	150+32	R2-1 -- 55 MPH	4.0	5.0	4.0	5.0					1			20.0		18			
NEB-WP-1033	153+41	R4-5X -- NO TRUCKS IN 2 LEFT LANES	4.0	6.0	4.0	6.0					1				24.0	18			
SWB-CL-1034A	154+19	GUIDE -- EXIT 4, IL RT 53 SOUTH/BIESTERFIELD RD, EXIT ONLY	19.5	13.0	19.5	13.0			253.5						253.5			3	25
SWB-PM-1034B	154+19	W13-3 -- 30 MPH	-	-	4.0	5.0								20.0					
SWB-WP-1037A	168+20	D9-2 -- BLUE BACKGROUND	2.5	2.5	2.5	2.5					1		6.3			18			
SWB-WP-1037B	168+20	SERVICE -- EXIT 4	-	-	2.5	1.3							3.1						
SWB-CL-1039	181+39	GUIDE -- EXIT 4, IL RT 52 SOUTH/BIESTERFIELD RD, EXIT ONLY	19.5	13.0	19.5	13.0			253.5						253.5			3	25
NEB-TR-1042A	191+22	GUIDE -- 90 CHICAGO/ROCKFORD 2 1/4 MILES	13.0	15.0	13.0	15.0			195.0						195.0			6	70
NEB-TR-1042B	191+22	GUIDE -- HIGGINS/WOODFIELD/GOLF 1 MILE EXIT ONLY	23.0	15.0	23.0	15.0			345.0						345.0				
SWB-CL-1044	206+78	GUIDE -- EXIT 4, IL RT 53 SOUTH/BIESTERFIELD RD, 1 MILE EXIT ONLY	19.5	15.0	19.5	15.0			292.5						292.5			3	25
NEB-WP-1047	212+85	GUIDE -- ILL INSTITUTE OF ART EXIT 1B	8.0	4.5	8.0	4.5					1				36.0	36			
NEB-CL-1048	218+57	GUIDE -- HIGGINS/WOODFIELD/GOLF EXIT ONLY	22.5	15.0	22.5	15.0			337.5						337.5			3	25
SWB-WP-1049	235+47	R2-1 -- 55 MPH	4.0	5.0	4.0	5.0					1			20.0		18			
SWB-WP-1050	237+43	R4-5X -- NO TRUCKS IN 2 LEFT LANES	4.0	6.0	4.0	6.0					1				24.0	18			
SWB-WP-1053A	239+88	M3-2 -- BLUE BACKGROUND	3.0	1.5	3.0	1.5					1		4.5			18			
SWB-WP-1053B	239+88	M1-1 -- 290	3.8	3.0	3.8	3.0								11.3					
SWB-WP-1053C	239+88	M3-3 -- WHITE BACKGROUND	3.0	1.5	3.0	1.5							4.5						
SWB-WP-1053D	239+88	M1-I100 -- IL 53	3.0	3.0	3.0	3.0							9.0						
NEB-TR-1054A	243+50	GUIDE -- 90 CHICAGO/ROCKFORD, 1 MILE	12.5	15.0	12.5	15.0			187.5						187.5			5	80
NEB-TR-1054B	243+50	GUIDE -- HIGGINS/WOODFIELD/GOLF EXIT ONLY	22.5	15.0	22.5	15.0			337.5						337.5				
NEB-WP-1055	246+40	W13-3 -- 45 MPH	4.0	5.0	4.0	5.0					1			20.0		18			
NEB-WP-1056	251+25	E5-1a -- EXIT 1B	7.5	5.0	7.5	5.0					1				37.5	36			
NEB-WP-1057	253+82	REC. & CULT. -- SCHAUMBURG CONVENTION CENTER KEEP RIGHT	8.0	5.5	8.0	5.5					1				44.0	36			
SWB-WP-1058	253+89	W4-3R -- ADDED LANE	4.0	4.0	4.0	4.0					1			16.0		18			

•F.A.I. 290 (INTERSTATE 290)
•F.A.U. 342 (IL ROUTE 53)

COPYRIGHT 2009, BY BAXTER & WOODMAN, INC.
STATE OF ILLINOIS PROFESSIONAL DESIGN FIRM
LICENSE NO. - 184-001121 - EXPIRES 4/30/2013
23Lukb 4:22:54 PM 7/2013 \\corpbaxwood.com\projects\CrystalLake\ILDOT\60053-WO-27-BAW.tbl ...\Standards\plotdrv\pdf-EDIT.plt ...\PLOTS\60053-WO-27-SIGN-SCHDLE.dgn

BAXTER & WOODMAN Consulting Engineers

USER NAME = 23lukb	DESIGNED - DJS	REVISED -	
	DRAWN - UKB	REVISED -	
PLOT SCALE = 1.0000 ' / in.	CHECKED - RWL	REVISED -	
PLOT DATE = 3/7/2012	DATE - 12-13-11	REVISED -	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.I RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
•	2011-024-SG	DuPAGE/COOK	132	4
		CONTRACT NO. 60P24		

FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT