

CONSTRUCTION CODE  
URBAN - FEDERAL 90% STATE 10%

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	SAFETY 0021
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	5	5
* 78200530	BARRIER WALL MARKERS, TYPE C	EACH	100	100
78300100	PAVEMENT MARKING REMOVAL	SQ FT	10,000	10,000
80400100	ELECTRIC SERVICE INSTALLATION	EACH	1	1
80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1	1
81028210	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2 1/2" DIA.	FOOT	30	30
81028220	UNDERGROUND CONDUIT, GALVANIZED STEEL, 3" DIA.	FOOT	500	500
81028250	UNDERGROUND CONDUIT, GALVANIZED STEEL, 5" DIA.	FOOT	2,550	2,550
81400200	HEAVY-DUTY HANDHOLE	EACH	5	5
81603081	UNIT DUCT, 600V, 3-1C NO.2, 1/C NO.4 GROUND, (XLP-TYPE USE), 1 1/2" DIA. POLYETHYLENE	FOOT	19,400	19,400
81702170	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 2/0	FOOT	150	150
81800320	AERIAL CABLE, 3-1/C NO. 4 WITH MESSENGER WIRE	FOOT	3,150	3,150
82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	1	1
82105700	LUMINAIRE, SODIUM VAPOR, HIGH MAST, HORIZONTAL MOUNT, 750 WATT	EACH	76	76
83057340	LIGHT POLE, WOOD, 60 FOOT, CLASS 3	EACH	14	14
83057345	LIGHT POLE, WOOD, 60 FOOT, CLASS 3, WITH 15FT MAST ARM	EACH	1	1
83504700	LIGHT TOWER, 120 FT. MOUNTING HEIGHT, LUMINAIRE MT. - 12	EACH	21	21
83506900	LIGHT TOWER, 140 FT. MOUNTING HEIGHT, LUMINAIRE MT. - 12	EACH	1	1
83700350	LIGHT TOWER FOUNDATION, 54" DIAMETER	FOOT	399	399
84200804	REMOVAL OF POLE FOUNDATION	EACH	11	11
84500110	REMOVAL OF LIGHTING CONTROLLER	EACH	1	1
84500120	REMOVAL OF ELECTRIC SERVICE INSTALLATION	EACH	1	1
84500130	REMOVAL OF LIGHTING CONTROLLER FOUNDATION	EACH	1	1

\* Specialty Items

m:\proj\10003384.dwg - High Mast Design\proposed\plan\3384\_L6\_US30\_High\_Mast.q35-500031.dgn



USER NAME = wjencoaster	DESIGNED - RJR	REVISED -
PLOT SCALE = 2.0000" = 1' IN.	DRAWN - RJR	REVISED -
PLOT DATE = 2/14/2012	CHECKED - JMV	REVISED -
	DATE - 02-14-2012	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

F.A.I. ROUTE 80 AT U.S. ROUTE 30 LIGHTING  
SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.I. RTE. 80	SECTION 2011-046-L	COUNTY WILL	TOTAL SHEETS 106	SHEET NO. 6
CONTRACT NO. 60P56			ILLINOIS FED. AID PROJECT	

Rev.