

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
				100% VILLAGE WATERMAIN IMPROVEMENTS 0043	STP FUNDS	
					75% FEDERAL/25% VILLAGE ROADWAY IMPROVEMENTS 0004	TRAINING 0042
60236800	INLETS, TYPE A, TYPE 11 FRAME AND GRATE	EACH	5		5	
60236825	INLETS, TYPE A, TYPE 11V FRAME AND GRATE	EACH	3		3	
60248700	VALVE VAULTS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	19	19		
60255500	MANHOLES TO BE ADJUSTED	EACH	13		13	
60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	2		2	
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	1		1	
60260100	INLETS TO BE ADJUSTED	EACH	4		4	
60265700	VALVE VAULTS TO BE ADJUSTED	EACH	3		3	
60500040	REMOVING MANHOLES	EACH	1		1	
60500050	REMOVING CATCH BASINS	EACH	1		1	
60500060	REMOVING INLETS	EACH	6		6	
60500105	FILLING MANHOLES	EACH	1		1	
60500205	FILLING CATCH BASINS	EACH	4		4	
60500305	FILLING INLETS	EACH	18		18	
60500405	FILLING VALVE VAULTS	EACH	9		9	
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	7905		7905	
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	2618		2618	
67100100	MOBILIZATION	L SUM	1		1	
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1		1	
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1		1	
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	1		1	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	9448		9448	
72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	30		30	
72400500	RELOCATE SIGN PANEL ASSEMBLY - TYPE A	EACH	30		30	
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	259		259	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	11921		11921	
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	947		947	
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	570		570	
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	237		237	
* 80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1		1	
* 80500100	SERVICE INSTALLATION, TYPE A	EACH	3		3	
* 81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	4912		4912	
* 81400100	HANDHOLE	EACH	3		3	

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
				100% VILLAGE WATERMAIN IMPROVEMENTS 0043	STP FUNDS	
					75% FEDERAL/25% VILLAGE ROADWAY IMPROVEMENTS 0004	TRAINING 0042
* 81702120	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 8	FOOT	7482		7482	
* 81702130	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6	FOOT	7050		7050	
* 82103150	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, PHOTO-CELL CONTROL, 150 WATT	EACH	37		37	
* 83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	185		185	
* 85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1		1	
* 85100100	PAINT EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	4		4	
* 87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	100		100	
* 88102747	PEDESTRIAN SIGNAL HEAD, LED, 2-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	4		4	
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	279		279	
* 88800100	PEDESTRIAN PUSH-BUTTON	EACH	8		8	
* 89502200	MODIFY EXISTING CONTROLLER	EACH	1		1	
* B2001116	TREE, CERCIS CANADENSIS (EASTERN REDBUD), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	4		4	
* B2001616	TREE, CRATAEGUS CRUSGALLI INERMIS (THORNLESS COCKSPUR HAWTHORN), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	4		4	
* B2006216	TREE, SYRINGA RETICULATA (JAPANESE TREE LILAC), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	6		6	
* B2010016	TREE, AMELANCHIER CANADENSIS (SHADBLOW SERVICEBERRY), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	7		7	
X4400110	TEMPORARY PAVEMENT REMOVAL	SQ YD	420		420	
* X5610004	DUCTILE IRON WATER MAIN FITTINGS	POUND	7,715	7,715		
* X5620030	WATER SERVICE CONNECTION 1"	EACH	45	45		
* X5620040	WATER SERVICE CONNECTION 2"	EACH	1	1		
X6026051	SANITARY MANHOLES TO BE RECONSTRUCTED	EACH	7		7	
* XX007548	GRANULAR CRADLE AND INITIAL BACKFILL	CU YD	131	131		
* XX008284	ORNAMENTAL LIGHT POLE, ALUMINUM WITH CONTEMPORARY ARM	EACH	37		37	
30300104	AGGREGATE SUBGRADE IMPROVEMENT 4"	SQ YD	1026		1026	
Z0016702	DETOUR SIGNING	L SUM	1		1	
Z0018900	DRILL AND GROUT DOWEL BARS	EACH	112	112		
Z0043750	PRECAST MODULAR BLOCK WALL	SQ FT	450		450	
Z0062456	TEMPORARY PAVEMENT	SQ YD	420		420	
* Z0073510	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	2		2	
Z0076600	TRAINEES	HOURLY	1000			1000

REVISIONS:
 FEBRUARY 7, 2012
 DECEMBER 30, 2011

FILE NAME: xxx	GERALD L. HEINZ & ASSOCIATES, INC. CONSULTING ENGINEERS & LAND SURVEYORS 206 NORTH RIVER STREET EAST DUNDEE, ILLINOIS 60118	USER NAME:	DESIGNED: EBW	REVISIONS: MARCH 23, 2011	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	FAU ROUTE: 2528	SECTION: 04-00043-00-PV	COUNTY: KANE	TOTAL SHEETS: 85	SHEET NO.: 4
		PLOT SCALE: NTS	CHECKED: JDH	REVISIONS: MAY 16, 2011			SCALE: 1"= 20'	SHEET NO. 2 OF 2 SHEETS	STA: TO STA:	FED. ROAD DIST. NO. ILLINOIS	FED. AID. PROJECT
		PLOT DATE:	DATE: AUGUST 25, 2010	REVISIONS: JUNE 2, 2011							
				REVISIONS: JULY 20, 2011							