



HORZ. 1"=40'

ARCHER AVENUE
CONTRACT BEGINS
AT STA 149+41

ARCHER AVENUE
CONTRACT ENDS
AT STA 164+00

- THERMOPLASTIC STRIPING CODE**
- A PROPOSED SOLID WHITE THERMOPLASTIC PAVEMENT MARKING - LINE 4" (EDGE LINE)
 - B PROPOSED DOUBLE SOLID YELLOW THERMOPLASTIC PAVEMENT MARKING - CENTERLINE 4" .11" O/C
 - C PROPOSED SOLID WHITE THERMOPLASTIC PAVEMENT MARKING - LINE 6" (CROSSWALK MARKING)
 - D PROPOSED SOLID WHITE THERMOPLASTIC PAVEMENT MARKING - LINE 6" (LANE LINE)
 - E PROPOSED SOLID WHITE THERMOPLASTIC PAVEMENT MARKING - LINE 8" (LANE AND EDGE LINE)
 - F PROPOSED SOLID YELLOW THERMOPLASTIC PAVEMENT MARKING - LINE 12", 45° DIAGONALS, (MEDIAN LINE)
 - G PROPOSED SOLID WHITE THERMOPLASTIC PAVEMENT MARKING - LINE 24" (STOP BAR)
 - H PROPOSED SOLID WHITE THERMOPLASTIC PAVEMENT MARKING - LETTERS & SYMBOLS
 - I PROPOSED SOLID WHITE THERMOPLASTIC PAVEMENT MARKING - LINE 12", 45° DIAGONALS, (MEDIAN LINE)
- REFLECTIVE PAVEMENT MARKERS**
- ON ARCHER AVENUE, EXISTING RAISED REFLECTIVE PAVEMENT MARKERS SHALL BE REMOVED AND REPLACED AS NECESSARY TO ACCOMMODATE NEW PAVEMENT MARKING CONFIGURATION. SEE DISTRICT DETAIL TC-11.

NOTE:
ALL "ARROWS" AND "ONLYS" SHALL BE 8" IN HEIGHT.

NOTE:
PROPOSED DOUBLE SOLID YELLOW THERMOPLASTIC PAVEMENT MARKING - CENTER LINE 4", .11" O/C (NOTE: A) IS MEASURED PER LINE. TOTAL QUANTITY AND PAYMENT LENGTH IS FOR EACH LINEAR FOOT OF SINGLE 4" STRIPE INSTALLED.

FOR RAISED REFLECTIVE PAVEMENT MARKING DETAILS
SEE SHEET 78 FOR DISTRICT DETAIL TC-11

FOR PAVEMENT MARKING DETAILS
SEE SHEET 79 FOR DISTRICT DETAIL TC-13

IMPORTANT!

FULL SIZE PLANS HAVE BEEN PREPARED USING STANDARD ENGINEERING SCALES.
REDUCED SIZED PLANS WILL NOT CONFORM TO STANDARD SCALES INDICATED IN TITLE BLOCK.

FILE NAME = FAU 1587 (MC CARTHY ROAD) FAP 577 (ARCHER AVENUE) FAU 1024 (DERBY ROAD) CHANNELIZATION AND TRAFFIC SIGNAL INSTALLATION	USER NAME =	DESIGNED - JLC	REVISED - THK 2-25-11
	PLOT SCALE =	DRAWN - JFP-JEP	REVISED -
	PLOT DATE =	CHECKED - THK	REVISED -
		DATE - 11/10	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

PLAN :
ARCHER AVENUE- (PAVEMENT MARKING)

SCALE: AS NOTED | SHEET NO. OF SHEETS | STA. 151+63 TO STA. 164+00

Frank Novotny & Associates, Inc.
Civil Engineers
185 Midway Drive • Willowbrook, IL • 60527 • Telephone: (630) 887-8640 • Fax: (630) 887-0133
ILLINOIS PROFESSIONAL DESIGN FIRM NO. 184-000285

F.A. -	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
RTE -	02-00055-00-WR	COOK	84	40
VAR	CONTRACT NO. 63557			
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT HPP-M-8003(504)		