



SCHEDULE OF QUANTITIES
ST. CHARLES ROAD AT RIFORD ROAD/ACKERMAN PARK

NO.	QUANT.	UNIT
1.	1 EACH	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION
2.	1 EACH	TRANSCIVER - FIBER OPTIC
3.	1 EACH	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT
4.	1 EACH	CONTROLLER (SPECIAL)



EXISTING EMERGENCY VEHICLE PREEMPTORS		
EMERGENCY VEHICLE PREEMPTOR	3	4
MOVEMENT	←	↑

I.D.O.T. TRAFFIC SIGNAL INSTALLATION ELECTRICAL SERVICE REQUIREMENTS					TOTAL WATTAGE
TYPE	NO. LAMPS	WATTAGE	% OPERATION		
SIGNAL (RED)	11	135	17	0.50	94.0
SIGNAL (YELLOW)	11	135	25	0.25	69.0
SIGNAL (GREEN)	11	135	15	0.25	42.0
ARROW	8	135	12	0.10	10.0
PED. SIGNAL	8	90	25	1.00	200.0
CONTROLLER	1	-	100	1.00	100.0
LUMINAIRE	2	250	-	0.50	250.0
I.L.E.D. ST. NAME SIGN	-	-	64	0.50	-
VIDEO SYSTEM	-	-	150	1.00	-
BATTERY BACKUP	-	-	25	1.00	-
ILLUMINATED SIGN	-	-	25	0.05	-
TOTAL =					765.0

ENERGY COSTS - BILLED TO: VILLAGE OF GLEN ELLYN
(ADDRESS) 20 S. LAMBERT ROAD
(ADDRESS) GLEN ELLYN, IL 60137
ENERGY SUPPLY - CONTACT: MS. DEB RANKIN
PHONE: (630) 691-4379
COMPANY: COM-ED

THE TRAFFIC SIGNAL CONTROL EQUIPMENT FOR THIS PROJECT SHALL BE "ECONOLITE" TO MATCH THE EXISTING ADJACENT SYSTEM.

FILE NAME = 4281.800-TR1.dwg	USER NAME = ZACH WALLSTEN	DESIGNED - JRD	REVISED -
PLOT SCALE = 1" = .0833'	CHECKED - KLB	DRAWN - ZCW	REVISED -
PLOT DATE = 12/16/2011	DATE - 12/16/2011		REVISED -

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES, CABLE PLAN, PHASE DESIGNATION DIAGRAM, & EMERGENCY VEHICLE PREEMPTION SEQUENCE
ST. CHARLES ROAD AT RIFORD ROAD/ACKERMAN PARK

FAU. RTE. 1397	SECTION 09-00206-08-TL	COUNTY DuPAGE	TOTAL SHEETS 53	SHEET NO. 25
CONTRACT # 63625				ILLINOIS FED. AID PROJECT