



LEGEND

- HMA PAVEMENT REPAIR
- CONCRETE SIDEWALK REMOVAL AND REPLACEMENT
- HOT MIX ASPHALT SURFACE REMOVE - BUTT JOINTS (10' UNLESS OTHERWISE INDICATED)
- HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4" POLYMERIZED LEVELING BINDER (MACHINE METHOD), N50, 3/4" HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70, 1 1/2"
- COMBINATION CURB AND GUTTER REMOVAL AND REPLACEMENT
- "A" CATCH BASIN TO BE ADJUSTED, MANHOLE TO BE ADJUSTED, VALVE BOX TO BE ADJUSTED, FRAME & LID TO BE ADJUSTED (SPECIAL)
- DETECTOR LOOP TO BE REPLACED
- EXISTING MANHOLE
- EXISTING CATCH BASIN

NOTES:

1. DETECTABLE WARNINGS ARE TO BE INSTALLED AT LOCATIONS OF SIDEWALK REMOVAL AND REPLACEMENT. CONTRACTOR TO POSITION AND PLACE DETECTABLE WARNINGS AT THE DIRECTION OF THE ENGINEER AND HIGHWAY STANDARDS IN ACCORDANCE WITH ADA REQUIREMENTS.
2. LIMIT OF CONSTRUCTION ON ALL SIDE STREETS IS THE RADIUS RETURN PLUS 10' BUTT JOINT OR ROW AS NOTED.
3. ACCESS TO ALL DRIVEWAYS SHALL BE MAINTAINED UPON COMPLETION OF EACH WORKDAY. RESIDENTS SHALL BE NOTIFIED 24 HOURS IN ADVANCE OF WHEN DRIVEWAY REPLACEMENT WILL TAKE PLACE.

FILE NAME = 11483-PLAN-01 - IDOT P01	USER NAME =	DESIGNED -- EER	REVISED --	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	STATE STREET RESURFACING LINCOLN AVENUE TO STATE-LINE ROAD PAVEMENT PLAN			F.A.U. RTE. 3596	SECTION 11-00150-00-RS	COUNTY COOK	TOTAL SHEETS 11	SHEET NO. 4
	PLOT SCALE =	CHECKED -- ###	REVISED --		SCALE: 1"=50'			SHEET NO. 4 OF 11 SHEETS			STA. 10+00 TO STA. 35+50	
	PLOT DATE = 09/29/11	DRAWN -- MED	REVISED --		CONTRACT NO. 63674							
		CHECKED -- ACAD	REVISED --		FED. ROAD DIST. NO. 1 ILLINOIS			FED. AID PROJECT TCSP-11(036)				