

SUMMARY OF QUANTITIES					CONSTRUCTION TYPE CODE
S.I.	CODE NO.	PAY ITEM	UNIT	QUAN	0005
	20101700	SUPPLEMENTAL WATERING	UNIT	1	1
	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	11	11
	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	11	11
	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	11	11
	25200110	SODDING, SALT TOLERANT	SQ YD	240	240
	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	2020	2020
	40600300	AGGREGATE (PRIME COAT)	TON	25	25
	40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	620	620
	40600895	CONSTRUCTING TEST STRIP	EACH	1	1
	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	330	330
	40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	930	930
	42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQ YD	30	30
	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	1500	1500
	42400800	DETECTABLE WARNINGS	SQ FT	300	300
	44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	10310	10310
	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	42	42
	44000600	SIDEWALK REMOVAL	SQ FT	1500	1500
	44201717	CLASS D PATCHES, TYPE II, 6 INCH	SQ YD	25	25
	44201721	CLASS D PATCHES, TYPE III, 6 INCH	SQ YD	50	50
	44201723	CLASS D PATCHES, TYPE IV, 6 INCH	SQ YD	170	170
	60200105	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	3	3
	60250200	CATCH BASINS TO BE ADJUSTED	EACH	14	14
	60253000	CATCH BASINS TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, OPEN LID	EACH	6	6
	60255500	MANHOLES TO BE ADJUSTED	EACH	15	15
	60266600	VALVE BOXES TO BE ADJUSTED	EACH	5	5
	60500050	REMOVING CATCH BASINS	EACH	3	3
	67100100	MOBILIZATION	L SUM	1	1

* - INDICATES SPECIALTY ITEMS

SUMMARY OF QUANTITIES					CONSTRUCTION TYPE CODE
S.I.	CODE NO.	PAY ITEM	UNIT	QUAN	0005
	70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1
	70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1
*	70300100	SHORT TERM PAVEMENT MARKING	FOOT	600	600
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	740	740
*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1030	1030
*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	240	240
	Z0004518	HOT-MIX ASPHALT DRIVEWAY PAVEMENT, 5"	SQ YD	12	12
	Z0004562	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	1020	1020

* - INDICATES SPECIALTY ITEMS

GENERAL NOTES

- BEFORE STARTING ANY EXCAVATION THE CONTRACTOR SHALL CALL "J.U.L.I.E." AT (800) 892-0123 AND (312) 744-7000 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE AND GAS UTILITIES. (48 HOUR NOTIFICATION REQUIRED)
- UTILITIES INDICATED ON THE PLANS ARE PROVIDED FOR THE CONTRACTORS USE AND ARE BASED UPON INFORMATION AVAILABLE AT THE TIME OF THE ADVERTISEMENT FOR BIDS. THE OWNER AND ENGINEER DO NOT GUARANTEE THE ACCURACY OF UTILITY INFORMATION.
- IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL DIMENSIONS AND CONDITIONS EXISTING IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING OF MATERIALS.
- THE THICKNESS OF HMA MIXTURE STATED IN THE SPECIFICATIONS IS THE NOMINAL THICKNESS. DEVIATIONS FROM THE NOMINAL THICKNESS WILL BE PERMITTED WHEN SUCH DEVIATIONS OCCUR DUE TO IRREGULARITIES IN THE EXISTING SURFACE OR BASE ON WHICH THE HMA SURFACE IS PLACED.
- ACCESS TO DRIVEWAYS SHALL BE MAINTAINED AT ALL TIMES BY LIMITING CURB AND GUTTER REPAIR TO ONE-HALF THE DRIVEWAY WIDTH AT ONE TIME AS WELL AS TEMPORARY AGGREGATE.
- THE REMOVAL AND/OR REPLACEMENT OF ANY DRIVEWAYS, PAVEMENT, CURB, SIDEWALK, ETC. SHALL BE ACCOMPLISHED BY MEANS OF A SAW CUT JOINT, AT THE DIRECTION OF THE ENGINEER. THIS WORK WILL NOT BE PAID FOR SEPARATELY, BUT SHALL BE INCLUDED IN THE UNIT PRICE FOR THE VARIOUS ITEMS.
- ANY LOOSE MATERIAL DEPOSITED IN THE FLOW LINE OF DITCHES, GUTTERS OR OTHER DRAINAGE STRUCTURES SHALL BE REMOVED BY THE END OF EACH DAY BY THE CONTRACTOR AT THEIR EXPENSE.
- FOR WORK OUTSIDE THE LIMITS OF BRIDGE APPROACH PAVEMENT, ALL REFERENCES IN THE HIGHWAY STANDARDS AND STANDARD SPECIFICATIONS FOR REINFORCEMENT, DOWEL BARS AND TIE BARS IN PAVEMENT, SHOULDERS, CURB, GUTTER, COMBINATION CURB AND GUTTER AND MEDIAN, AND CHAIR SUPPORTS FOR CRC PAVEMENT, SHALL BE EPOXY COATED, UNLESS OTHERWISE NOTED ON THE PLAN.

FILE NAME = 11278-QUAN-01 - P01

USER NAME =	DESIGNED -- RES	REVISED --
	CHECKED -- PKB	REVISED --
PLOT SCALE =	DRAWN -- MED	REVISED --
PLOT DATE = 1-31-12	CHECKED -- AG	REVISED --

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ELLIS AVENUE RESURFACING
LINCOLN AVE TO 142ND ST
SUMMARY OF QUANTITIES & GENERAL NOTES

SCALE: NONE SHEET NO. 2 OF 11 SHEETS STA. TO STA.

F.A.U. RITE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1043	11-00115-00-RS	COOK	11	2
FED. ROAD DIST. NO. 1 ILLINOIS			FED. AID PROJECT M-9003(909)	
CONTRACT NO. 63676				