

SUMMARY OF QUANTITIES				
S.I. CODE NO.	PAY ITEM	UNIT	QUAN	CONSTRUCTION TYPE CODE 0005
20101700	SUPPLEMENTAL WATERING	UNIT	2	2
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	156	156
25200110	SODDING, SALT TOLERANT	SQ YD	156	156
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	2245	2245
40600300	AGGREGATE (PRIME COAT)	TON	23	23
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	489	489
40600895	CONSTRUCTING TEST STRIP	EACH	1	1
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	452	452
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	975	975
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQ YD	70	70
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	610	610
42400800	DETECTABLE WARNINGS	SQ FT	200	200
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	11153	11153
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	104	104
44000600	SIDEWALK REMOVAL	SQ FT	610	610
44201725	CLASS D PATCHES, TYPE I, 7 INCH	SQ YD	10	10
44201729	CLASS D PATCHES, TYPE II, 7 INCH	SQ YD	34	34
44201733	CLASS D PATCHES, TYPE III, 7 INCH	SQ YD	111	111
44201735	CLASS D PATCHES, TYPE IV, 7 INCH	SQ YD	126	126
60250200	CATCH BASINS TO BE ADJUSTED	EACH	16	16
60255500	MANHOLES TO BE ADJUSTED	EACH	1	1
60266600	VALVE BOXES TO BE ADJUSTED	EACH	1	1
67100100	MOBILIZATION	L SUM	1	1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1
70300100	SHORT TERM PAVEMENT MARKING	FOOT	735	735
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	930	930

\* - INDICATES SPECIALTY ITEMS

SUMMARY OF QUANTITIES				
S.I. CODE NO.	PAY ITEM	UNIT	QUAN	CONSTRUCTION TYPE CODE 0005
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	260	260
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	115	115
X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	1	1
Z0004518	HOT-MIX ASPHALT DRIVEWAY PAVEMENT, 5"	SQ YD	36	36
Z0004562	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	800	800

\* - INDICATES SPECIALTY ITEMS

GENERAL NOTES

- BEFORE STARTING ANY EXCAVATION THE CONTRACTOR SHALL CALL "J.U.L.I.E." AT (800) 892-0123 AND (312) 744-7000 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE AND GAS UTILITIES. (48 HOUR NOTIFICATION REQUIRED)
- UTILITIES INDICATED ON THE PLANS ARE PROVIDED FOR THE CONTRACTORS USE AND ARE BASED UPON INFORMATION AVAILABLE AT THE TIME OF THE ADVERTISEMENT FOR BIDS. THE OWNER AND ENGINEER DO NOT GUARANTEE THE ACCURACY OF UTILITY INFORMATION.
- IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL DIMENSIONS AND CONDITIONS EXISTING IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING OF MATERIALS.
- THE THICKNESS OF HMA MIXTURE STATED IN THE SPECIFICATIONS IS THE NOMINAL THICKNESS. DEVIATIONS FROM THE NOMINAL THICKNESS WILL BE PERMITTED WHEN SUCH DEVIATIONS OCCUR DUE TO IRREGULARITIES IN THE EXISTING SURFACE OR BASE ON WHICH THE HMA SURFACE IS PLACED.
- ACCESS TO DRIVEWAYS SHALL BE MAINTAINED AT ALL TIMES BY LIMITING CURB AND GUTTER REPAIR TO ONE-HALF THE DRIVEWAY WIDTH AT ONE TIME AS WELL AS TEMPORARY AGGREGATE.
- THE REMOVAL AND/OR REPLACEMENT OF ANY DRIVEWAYS, PAVEMENT, CURB, SIDEWALK, ETC. SHALL BE ACCOMPLISHED BY MEANS OF A SAW CUT JOINT, AT THE DIRECTION OF THE ENGINEER. THIS WORK WILL NOT BE PAID FOR SEPARATELY, BUT SHALL BE INCLUDED IN THE UNIT PRICE FOR THE VARIOUS ITEMS.
- ANY LOOSE MATERIAL DEPOSITED IN THE FLOW LINE OF DITCHES, GUTTERS OR OTHER DRAINAGE STRUCTURES SHALL BE REMOVED BY THE END OF EACH DAY BY THE CONTRACTOR AT THEIR EXPENSE.
- FOR WORK OUTSIDE THE LIMITS OF BRIDGE APPROACH PAVEMENT, ALL REFERENCES IN THE HIGHWAY STANDARDS AND STANDARD SPECIFICATIONS FOR REINFORCEMENT, DOWEL BARS AND TIE BARS IN PAVEMENT, SHOULDERS, CURB, GUTTER, COMBINATION CURB AND GUTTER AND MEDIAN, AND CHAIR SUPPORTS FOR CRC PAVEMENT, SHALL BE EPOXY COATED, UNLESS OTHERWISE NOTED ON THE PLAN.

FILE NAME = 11427-QUAN-01 - IDOT QUAN	USER NAME =	DESIGNED -- DWS	REVISED --	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	DANTE AVENUE IMPROVEMENTS SUMMARY OF QUANTITIES & GENERAL NOTES	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
		CHECKED -- JH/PB	REVISED --			1072	11-00054-00-RS	COOK	10	2	
	PLOT SCALE =	DRAWN -- MED	REVISED --			CONTRACT NO. 63679					
	PLOT DATE = 1-31-12	CHECKED -- AG	REVISED --			SCALE: NONE	SHEET NO. 2 OF 10 SHEETS	STA. TO STA.	FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT M-9003(906)		