

# SCHEDULE OF QUANTITIES

PAINT PAVEMENT MARKING - LINE 4"			78001110
Stage I			
EASTBOUND			FOOT
WHITE	81+58.00	89+47.00	789
YELLOW	81+52.00	81+91.00	39
WESTBOUND			
YELLOW	89+85.00	90+55.00	70
WHITE	82+52.00	90+47.00	795
YELLOW	82+20.00	82+50.00	30
Stage 2			
EASTBOUND			
YELLOW	81+80.00	91+25.00	945
WESTBOUND			
YELLOW	80+75.00	90+15.00	940
WHITE	95+00.00	95+70.00	70
TOTAL			3,678
FOR 2 COATS OF PAINT USE			7,356

PAINT PAVEMENT MARKING - LINE 12"			78001150
Stage I			
EASTBOUND			FOOT
CHEVRONS	82+00.00	84+00.00	57
CHEVRONS	88+50.00	89+50.00	16
DIAGONALS	89+50.00	91+00.00	45
WESTBOUND			
DIAGONALS	80+45.00	82+50.00	73
CHEVRONS	82+50.00	83+47.00	33
CHEVRONS	88+80.00	90+00.00	32
DIAGONALS	90+00.00	90+55.00	32
CHEVRONS	95+70.00	99+37.00	140
TOTAL			428
FOR 2 COATS OF PAINT USE			856

TEMPORARY CONCRETE BARRIER			70400100
Stage I			
83+19.44	87+74.57		450
84+30.27	89+11.06		475
TOTAL			925

RELOCATE TEMPORARY CONCRETE BARRIER			70400200
Stage II			
82+89.41	87+69.58		475
84+15.22	88+70.82		450
TOTAL			925

PAINT PAVEMENT MARKING - LINE 6"			78001130
Stage I			
EASTBOUND			FOOT
SKIP-DASH	70+70.00	91+00.00	508
SKIP-DASH	84+55.00	87+68.00	78
WESTBOUND			
SKIP-DASH	80+45.00	109+00.00	714
SKIP-DASH	83+47.00	87+19.00	93
TOTAL			1,393
FOR 2 COATS OF PAINT USE			2,786

SHOULDER RUMBLE STRIPS, 16 INCH			64200116
FOOT			
EB OUT	82+30.00	84+75.00	245
EB OUT	87+05.00	89+45.00	240
EB MED	82+00.00	84+76.00	276
EB MED	87+10.00	90+65.00	355
WB MED	81+80.00	84+84.00	304
WB MED	87+18.00	90+65.00	347
WB OUT	82+40.00	84+90.00	250
WB OUT	87+20.00	89+50.00	230
TOTAL			2247

IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3			Z0030250
Stage I			
83+19.00	RT.		1
89+11.00	LT.		1
TOTAL			2

IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3			Z0030350
Stage II			
82+89.00	RT.		1
88+71.00	LT.		1
TOTAL			2

PAINT PAVEMENT MARKING - LINE 8"			78001140
EASTBOUND			
WHITE	81+00.00	84+55.00	355
WHITE	87+68.00	91+00.00	332
WHITE	81+91.00	84+55.00	264
WHITE	88+58.00	89+50.00	92
WESTBOUND			
WHITE	80+45.00	83+47.00	302
WHITE	87+19.00	90+55.00	336
WHITE	82+50.00	83+47.00	97
WHITE	88+80.00	89+85.00	105
WHITE	95+70.00	99+37.00	367
WHITE	95+70.00	99+37.00	367
TOTAL			2,617
FOR 2 COATS OF PAINT USE			5,234

TEMPORARY PAVEMENT			Z0062456
EACH			
82+23.00	LT.		9
89+53.00	RT.		3
TOTAL			12

DATE	BY	DATE
NO.	NO.	NO.

DATE	BY	DATE
NO.	NO.	NO.

FILE NAME =D264H71-aht-schedule02.dgn  
 PLOT DATE =1/24/2012  
 PLOT SCALE=50,0000' / IN.

**CHRISTIAN-ROGE & ASSOCIATES, INC.**  
 ENGINEERS-PLANNERS-SURVEYORS  
 211 WEST WACKER DRIVE  
 CHICAGO, ILLINOIS 60606  
 PHONE: (312)372-2023 FAX: (312)372-5274

DESIGNED -	G.F.L./K.R.K.	REVISED -	
DRAWN -	K.R.K.	REVISED -	
CHECKED -	E.J.M.	REVISED -	
DATE -	JANUARY 2012	REVISED -	

**STATE OF ILLINOIS**  
**DEPARTMENT OF TRANSPORTATION**

**SCHEDULE OF QUANTITIES - IL ROUTE 5 AT I-74**

SCALE: NONE SHEET NO. 1 OF 1 SHEETS STA. TO STA.

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
205	(81-2HB-1)M	ROCK ISLAND	29	5
CONTRACT NO. 64H71				
ILLINOIS				