

PAVEMENT MARKING SCHEDULE													
LOCATION	70300220	70301000	78005110	78005130	78005140	78100100	78100105	78100200	78300100	78300200	COLOR	NOTE	LOCATION
	TEMPORARY PAVEMENT MARKING - LINE 4"	WORK ZONE PAVEMENT MARKING REMOVAL	EPOXY PAVEMENT MARKING - LINE 4"	EPOXY PAVEMENT MARKING - LINE 6"	EPOXY PAVEMENT MARKING - LINE 8"	RAISED REFLECTIVE PAVEMENT MARKER	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	TEMPORARY RAISED REFLECTIVE PAVEMENT MARKER	PAVEMENT MARKING	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL			
	FOOT	SQ FT	FOOT	FOOT	FOOT	EACH	EACH	EACH	SQ FT	EACH			
STAGE 2													
2361+00.00	2441+12.50	8013	2671								Yellow	Solid edge line	NB lane on LT
2398+00.00	2443+62.50	4563	1521								White	Solid edge line	NB lane on RT
2401+00.00	2447+00.00	4615	1538								Yellow	Solid edge line	SB lane on LT thru crossover
2403+13.00	2473+50.00	7068	2356								White	Solid edge line	SB lane on RT thru crossover
2398+00.00	2443+62.50			4563							White		NB outside edge
2401+00.00	2447+00.00			4600							Yellow		NB inside edge
2405+35.00	2448+62.50			4328							White		SB outside edge
2401+00.00	2447+00.00			4600							Yellow		SB inside edge
2361+00.00	2371+00.00				250						White		NB center skip
2419+11.00	2430+70.00				290						White		NB center skip
2418+30.00	2431+55.00				330						White		SB center skip
2463+50.00	2473+50.00				250						White		SB center skip
2377+06.00	2378+23.00					117					White		NB gore edge
16+43.50	17+60.20					117					White		Baster Ramp gore edge
2361+00.00	2371+00.00						13						NB lanes
2430+44.00	2430+69.00						1						NB lanes
2418+30.00	2419+60.00						2						SB lanes
2463+50.00	2473+50.00						13						SB lanes
2418+81.00	2430+44.00							30					NB Bridge
2419+60.00	2431+30.00							30					SB Bridge
2398+00.00	2419+11.00								704				NB edge RT
2430+01.00	2443+62.50								454				NB edge RT
2404+00.00	2419+11.00								504				NB edge LT
2430+01.00	2443+00.00								433				NB edge LT
2401+00.00	2405+00.00								133				SB edge LT
2442+00.00	2447+00.00								167				SB edge LT
2418+30.00	2431+55.00									17			SB bridge & approach
2361+00.00	2380+00.00							48					NB LT
2380+00.00	2410+00.00							76					NB LT
2398+00.00	2410+00.00							30					NB RT
2401+00.00	2409+38.20								42				SB LT
2403+13.00	2409+38.20								34	42			SB RT
2409+38.20	2410+00.00								2				SB RT
2410+00.00	2415+97.70								15				NB RT
2410+00.00	2419+81.00								22				SB RT
2430+44.00	2440+00.00								24				NB RT
2433+37.20	2438+61.90								13				SB RT
2439+00.00	2440+00.00								5				SB LT
2438+61.90	2440+00.00									7			SB LT
2438+61.90	2440+00.00												SB RT
2440+00.00	2443+62.50									9			NB RT
2440+00.00	2447+00.00									35			SB LT
2440+00.00	2447+00.00									35			SB RT
2447+00.00	2470+00.00									58			SB RT
2470+00.00	2473+50.00									9			SB RT
	SUBTOTAL	24259	8086	18091	1120	234	29	60	418 168	2395	17		
	TOTALS	49055	16351	18091	1120	234	29	60	820 336	5626	58		

