

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				STATE FUNDS	100% STATE STRUCTURE
				0014	RURAL
50102400	CONCRETE REMOVAL	CU YD	16.7		16.7
50300255	CONCRETE SUPERSTRUCTURE	CU YD	11.6		11.6
50300260	BRIDGE DECK GROOVING	SQ YD	111		111
50300300	PROTECTIVE COAT	SQ YD	111		111
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	3100		3100
50800515	BAR SPLICERS	EACH	22		22
50800530	MECHANICAL SPLICERS	EACH	62		62
50901050	STEEL RAILING, TYPE SM	FOOT	62		62
* 63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	1		1
63200310	GUARDRAIL REMOVAL	FOOT	180		180
67100100	MOBILIZATION	L SUM	1		1
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1		1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1		1
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1		1
70400100	TEMPORARY CONCRETE BARRIER	FOOT	211		211
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	211		211
78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	31		31
78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	4		4
X0326519	STEEL RAILING, REMOVAL	FOOT	62		62
X5030275	CONCRETE WEARING SURFACE REMOVAL	SQ YD	90		90
X5030306	CONCRETE WEARING SURFACE 6"	SQ YD	111		111
X7200201	WIDTH RESTRICTION SIGNING	L SUM	1		1
Z0012102	CONCRETE BRIDGE DECK SCARIFICATION (3/8")	SQ YD	90		90
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2		2
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2		2
Z0043900	PREFORMED JOINT FILLER	FOOT	10		10

*SPECIALITY ITEMS

FILE NAME :	USER NAME = potelyj	DESIGNED - RON WOODSHANK	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwork\pwork\potelyj\d8298048\0366	74-sht-details.dgn	DRAWN - RON WOODSHANK	REVISED -					796	(104B)-1	KANKAKEE	12	3
	PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -		SCALE:	SHEET NO. 1 OF 1 SHEETS	STA.	TO STA.	CONTRACT NO. 66B94			
	PLOT DATE = 2/16/2012	DATE -	REVISED -		ILLINOIS FED. AID PROJECT							

Rev.