

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE
				90% FED 10% STATE ROADWAY 0005 URBAN
70300100	SHORT TERM PAVEMENT MARKING	FOOT	1882	1882
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	621	621
△ 78009004	MODIFIED URETHANE PAVEMENT MARKING - LINE 4"	FOOT	43880	43880
△ 78009008	MODIFIED URETHANE PAVEMENT MARKING - LINE 8"	FOOT	1751	1751
△ 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	30	30
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	30	30
X0326880	MESSAGE BOARD VEHICLE DRIVER	HOUR	160	160
X0326907	PORTABLE, VEHICLE MOUNTED, CHANGEABLE MESSAGE SIGN	CAL MO	2	2
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SO YD	68670	68670
X7010805	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401 (SPECIAL)	L SUM	1	1
△ X7830070	GROOVING FOR RECESSED PAVEMENT MARKING 5"	FOOT	43880	43880
△ X7830076	GROOVING FOR RECESSED PAVEMENT MARKING 9"	FOOT	1751	1751
Z0034105	MATERIAL TRANSFER DEVICE	TON	12370	12370

△ SPECIALTY ITEMS

FILE NAME =	USER NAME = duncanbd	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwwork\pwwork\duncanbd\0292276\036896-shr-500.dgn	DRAWN -	REVISED -	55					D3 INTERMITTENT RS 2012-1	LIVINGSTON	8	4	
PLOT SCALE = 100.0000' / 1"	CHECKED -	REVISED -	SCALE: SHEET NO. OF SHEETS STA. TO STA.					CONTRACT NO. 66B96				
PLOT DATE = 2/9/2012	DATE -	REVISED -	ILLINOIS FED. AID PROJECT									