

MODIFIED URETHANE PAVEMENT MARKING												
LOCATION	WHITE LINE 4"	WHITE LINE 6"	WHITE LINE 8"	WHITE LINE 12"	WHITE LINE 24"	YELLOW LINE 4"	YELLOW LINE 12"	YELLOW SKIP DASH 4"	LETTERS & SYMBOLS	RPMS ONE WAY	RPMS TWO WAY	RPMS REMOVAL
IL 78 (LOCUST ST.)												
STA. 24+56 TO STA. 26+13					12 FT.	628 FT.	104 FT.				8	8
STA. 26+48 TO STA. 26+98					12 FT.	200 FT.						
TURN LANE AND MEDIAN		48 FT.	302 FT.	98 FT.					15.6 FT.	4		4
IL 78 (5TH AVE)												
STA. 25+52 TO STA. 25+82					12 FT.	120 FT.						
STA. 26+42 TO STA. 30+21	60 FT.	182 FT.	319 FT.		61 FT.	1128 FT.	151 FT.		31.2 FT.	12	14	26
STA. 31+17 TO STA. 35+36	40 FT.	120 FT.	200 FT.		24 FT.	970 FT.		111.3 FT.	62.4 FT.	7	22	29
STA. 36+02 TO STA. 39+32						792 FT.		220 FT.	31.2 FT.		18	18
STA. 39+98 TO STA. 44+12						938 FT.		276 FT.	62.4 FT.		22	22
STA. 44+67 TO STA. 47+61						720 FT.		196 FT.	31.2 FT.		16	16
STA. 48+27 TO STA. 51+06						690 FT.		186 FT.	31.2 FT.		14	14
STA. 51+72 TO STA. 54+28						512 FT.		170.6 FT.	170 FT.		16	16
STA. 54+94 TO STA. 58+00						612 FT.		204 FT.	31.2 FT.		16	16
STA. 58+47 TO STA. 62+20						746 FT.		248.6 FT.	62.4 FT.		18	18
STA. 62+73 TO STA. 66+34						722 FT.		240.6 FT.	31.2 FT.		16	16
STA. 66+93 TO STA. 70+69		98 FT.	200 FT.		26 FT.	1292 FT.	65 FT.	70.6 FT.	62.4 FT.	4	16	20
STA. 71+39 TO STA. 74+47		174 FT.			12 FT.	1232 FT.	65 FT.				16	16
STA. 74+85 TO STA. 78+07		152 FT.						107.3 FT.			4	4
STA. 78+49 TO STA. 81+11		152 FT.						87.3 FT.			3	3
STA. 81+51 TO STA. 84+14		38 FT.						87.6 FT.			3	3
STA. 84+42 TO STA. 96+54	2424 FT.							404 FT.			16	16
SIDE STREETS												
CHESTNUT STREET		544 FT.			24 FT.	76 FT.						
ELM STREET		368 FT.			24 FT.	30 FT.						
PINE STREET		198 FT.			24 FT.	40 FT.						
WALNUT STREET		272 FT.			24 FT.	40 FT.						
MAPLE STREET		280 FT.			24 FT.	60 FT.						
ANDERSON STREET		142 FT.			12 FT.	80 FT.						
GRANT STREET		126 FT.			12 FT.							
OAK STREET		262 FT.			24 FT.							
HICKORY STREET		294 FT.			24 FT.	60 FT.						
CHERRY STREET		266 FT.			24 FT.	64 FT.						
LINN STREET (IL 9)		264 FT.	109 FT.	38 FT.	67 FT.	840 FT.	65 FT.	120 FT.	78 FT.	4	14	18
HOLLY STREET		256 FT.			24 FT.							
LEWIS STREET		270 FT.			24 FT.							
HANLON STREET		288 FT.			24 FT.							
SAM SCOTT STREET					36 FT.							
TOTAL	2524 FT.	4794 FT.	930 FT.	136 FT.	550 FT.	12592 FT.	450 FT.	2729 FT.	638 FT.	31 EA.	252 EA.	283 EA.

USER NAME = eppenzeller,jj
 PLOT SCALE = 1/8" = 1' / in.
 PLOT DATE = 2/1/2012

DESIGNED - _____
 DRAWN - _____
 CHECKED - _____
 DATE - _____

REVISED - _____
 REVISED - _____
 REVISED - _____
 REVISED - _____

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: _____ SHEET NO. _____ OF _____ SHEETS STA. _____ TO STA. _____

F.A.P. RTE. 22	SECTION 135((Z)RS-2,(X)RS-1)	COUNTY FULTON	TOTAL SHEETS 33	SHEET NO. 22
CONTRACT NO. 68978			ILLINOIS FED. AID PROJECT	