

URBAN

80% FED  
20% STATE

CODE NO.	SUMMARY OF QUANTITIES ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
				ROADWAY 0001	BRIDGE 0008	LIGHTING 0021
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	1	1		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	22,276	22,276		
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	941	941		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	4,684	4,684		
* 78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	5,939	5,939		
• 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	8	8		
• 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	6		6	
• 78200410	GUARDRAIL MARKERS, TYPE A	EACH	7	7		
• 78200530	BARRIER WALL MARKERS, TYPE C	EACH	8		8	
• 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	2	2		
78300100	PAVEMENT MARKING REMOVAL	SQ FT	671	671		
81200230	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., PVC	FOOT	540			540
81300835	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 18"x18"x10"	EACH	4			4
X0325598	DRAINAGE SCUPPERS, DS-12M10	EACH	6		6	
X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	327		327	
X6024505	INLETS TO BE RECONSTRUCTED WITH SALVAGED FRAME AND GRATE	EACH	1	1		
X6050500	REMOVE FRAME AND GRATES, SPECIAL	EACH	1	1		
X6020082	INLETS, TYPE G-1	EACH	1	1		
X2090215	SELECT GRANULAR BACKFILL, SPECIAL	CU YD	115	115		
Z0001002	GUARDRAIL AGGREGATE EROSION CONTROL	TON	179	179		
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1		
Z0022800	FENCE REMOVAL	FOOT	2,655	2,655		
Z0046304	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	240		240	
Z0062456	TEMPORARY PAVEMENT	SQ YD	4,875	4,875		

• SPECIALTY ITEM