

## SUMMARY OF QUANTITIES

LOCATION OF WORK: FAS 533 (MARKET ST)  
 RURAL  
 COUNTY: CHAMPAIGN  
 STA 106+50.00  
 TO  
 STA 162+24.00  
 FUNDING BREAKOUT: 80% FEDERAL  
 20% STATE  
 CONSTRUCTION TYPE CODE: 0005

CODE NO	ITEM	UNIT	TOTAL QUANTITY
67100100	MOBILIZATION	L SUM	1.0
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1.0
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1.0
70300100	SHORT TERM PAVEMENT MARKING	FOOT	1,000.0
70300220	TEMPORARY PAVEMENT MARKING LINE - 4"	FOOT	11,239.0
70300280	TEMPORARY PAVEMENT MARKING LINE - 24"	FOOT	40.0
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	165.0
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	15,380.0
* 78001180	PAINT PAVEMENT MARKING - LINE 24"	FOOT	40.0
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	65.0
X4400196	HOT-MIX ASPHALT SURFACE REMOVAL, SPECIAL	SQ YD	1,738.0
X4421000	PARTIAL DEPTH PATCHING	TON	149.0
X2020110	GRADING AND SHAPING SHOULDERS	UNIT	89.0
Z0070100	SURVEY MONUMENT COVER ASSEMBLY	EACH	5.0

\* DENOTES SPECIALTY ITEM

FILE NAME =	USER NAME = piersnbr	DESIGNED - SEL	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>			F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ei\pwwork\pwwork\piersonbr\d0249274\05	70874-sht-S00.dgn	DRAWN - BBP	REVISED -					533	(10-34,HB-5,106)RS-1	CHAMPAIGN	26	5
	PLOT SCALE = 40.0000 ' / in.	CHECKED -	REVISED -		CONTRACT NO. 70874			ILLINOIS FED. AID PROJECT				
	PLOT DATE = 1/27/2012	DATE - 02/24/11	REVISED -		SCALE: NONE	SHEET NO. 2 OF 2 SHEETS	STA.	TO STA.				