

SUMMARY OF QUANTITIES

CONSTRUCTION CODE

0005

MENARD ROADWAY 80% FEDERAL 20% STATE	MASON ROADWAY 80% FEDERAL 20% STATE
---	--

CODE NO.	ITEM	UNIT	TOTAL QUANTITY		
20200100	EARTH EXCAVATION	CU YD	3728.5		3,728.50
20200600	EXCAVATING AND GRADING EXISTING SHOULDER	UNIT	537.6		537.6
* 25000200	SEEDING, CLASS 2	ACRE	0.92		0.92
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	82		82
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	82		82
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	82		82
* 25000700	AGRICULTURAL GROUND LIMESTONE	TON	1.9		1.9
* 25100115	MULCH, METHOD 2	ACRE	0.5		0.5
* 25100635	HEAVY DUTY EROSION CONTROL BLANKET	SQ YD	347		347
28000315	AGGREGATE DITCH CHECKS	TON	4.5		4.5
28100125	STONE RIPRAP, CLASS B3	SQ YD	1167		1,167
28100207	STONE RIPRAP, CLASS A4	TON	21		21
28200200	FILTER FABRIC	SQ YD	636		636
31101000	SUBBASE GRANULAR MATERIAL, TYPE B	TON	576.4		576.4

* SPECIALTY ITEM

*(E)RS-4,(G)RS-6)& (F)RS-3, 1-1
**MASON, MENARD

FILE NAME =	USER NAME = sparksgv	DESIGNED - ETJ	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ct:\pw\work\p\idat\sparksgv\d0283522\067	2F04-shr-500.dgn	DRAWN - ETJ	REVISED -			658	.	**	106	3	
	PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -			CONTRACT NO. 72F04					
	PLOT DATE = Feb-27-2012 02:00:49PM	DATE - 02-24-12	REVISED -			ILLINOIS FED. AID PROJECT					

SCALE: SHEET 1 OF 6 SHEETS STA. TO STA.