

PAINT PAVEMENT MARKING - LINE 5''		CENTERLINE-YELLOW		EDGE LINE-WHITE		TOTAL
LOCATION	LENGTH (FEET)	TYPE	LENGTH (FEET)	LENGTH (FEET)	LENGTH (FEET)	(FEET)
IL 29 (MENARD COUNTY)						
STA 732+15.94 TO STA 732+50.94	35	DOUBLE YELLOW	70	70		
STA 732+49.96 TO STA 750+02.00	1752	DOUBLE YELLOW	3504	3504		
STA 750+02.00 TO STA 750+37.00	35	DOUBLE YELLOW	70	70		
MENARD COUNTY TOTAL	1822		3644	3644		7288
IL 29 (MASON COUNTY)						
STA 750+37.00 TO STA 764+39.00		STRUCTURE OMISSION - 065-0501				
STA 764+39.00 TO STA 783+73.96	1935	DOUBLE YELLOW	490	3870		
STA 783+73.96 TO STA 784+49.53	76	SKIP DASH	20	152		
STA 33+22.93 TO STA 43+14.36	991	SKIP DASH	250	1982		
STA 43+14.36 TO STA 48+39.36	525	NO PASSING - NB	665	1050		
STA 48+39.36 TO STA 63+15.36	1476	DOUBLE YELLOW	2952	2952		
STA 63+15.36 TO STA 72+60.36	945	NO PASSING - SB	1185	1890		
STA 72+60.36 TO STA 77+74.36	514	SKIP DASH	130	1028		
STA 77+74.36 TO STA 83+15.36	541	NO PASSING - NB	681	1082		
STA 83+15.36 TO STA 87+78.36	463	SKIP DASH	120	926		
STA 87+78.36 TO STA 91+77.36	399	NO PASSING - SB	499	798		
STA 91+77.36 TO STA 93+27.36	150	SKIP DASH	40	300		
STA 93+27.36 TO STA 103+71.36	1044	NO PASSING - NB	1314	2088		
STA 103+71.36 TO STA 106+12.36	241	DOUBLE YELLOW	482	482		
STA 106+12.36 TO STA 115+25.36	913	NO PASSING - SB	1143	1826		
STA 115+25.36 TO STA 162+94.36	4769	SKIP DASH	1200	9538		
STA 162+94.36 TO STA 172+37.36	943	NO PASSING - NB	1183	1886		
STA 172+37.36 TO STA 174+18.36	181	DOUBLE YELLOW	362	362		
STA 174+18.36 TO STA 180+78.36	660	NO PASSING - SB	830	1320		
STA 180+78.36 TO STA 186+98.36	620	SKIP DASH	160	1240		
STA 186+98.36 TO STA 196+96.36	998	NO PASSING - NB	1248	1996		
STA 196+96.36 TO STA 200+28.36	332	DOUBLE YELLOW	664	664		
STA 200+28.36 TO STA 203+49.36	321	NO PASSING - SB	411	642		
STA 203+49.36 TO STA 259+30.36	5581	SKIP DASH	1400	11162		
STA 259+30.36 TO STA 263+11.04	381	NO PASSING - NB	481	762		
STA 263+11.04 TO STA 265+11.74	197	NO PASSING - NB	247	394		
MASON COUNTY TOTAL	25196		18157	50392		68549
PROJECT TOTAL						75837

RAISED REFLECTIVE PAVEMENT MARKER				LANE LOCATION	COLOR	TOTAL EACH
IL 29 (MENARD COUNTY)						
STA 732+15.94 TO STA 750+37.00		CENTERLINE	AMBER			23
MENARD COUNTY TOTAL						23
IL 29 (MASON COUNTY)						
STA 750+37.00 TO STA 764+39.00		STRUCTURE OMISSION - 065-0501				
STA 764+39.00 TO STA 784+49.53		CENTERLINE	AMBER			26
STA 33+22.93 TO STA 263+11.04		CENTERLINE	AMBER			288
STA 263+14.42 TO STA 270+00.00		CENTERLINE	AMBER			9
IL 29 AT INTERSECTION						
STA 270+00.00 TO STA 276+90.00		CENTERLINE	AMBER			32
STA 276+90.00 TO STA 287+33.48		CENTERLINE	AMBER			28
IL 10 AT INTERSECTION						
STA 0+00.00 TO STA 11+18.00		CENTERLINE	AMBER			21
STA 0+00.00 TO STA 6+47.38		CENTERLINE	AMBER			22
MASON COUNTY TOTAL						426
		PROJECT TOTAL				449

RAISED REFLECTIVE PAVEMENT MARKER REMOVAL				LANE LOCATION	COLOR	TOTAL EACH
IL 29 (MENARD COUNTY)						
STA 732+15.94 TO STA 750+37.00		CENTERLINE	AMBER			23
MENARD COUNTY TOTAL						23
IL 29 (MASON COUNTY)						
STA 750+37.00 TO STA 764+39.00		STRUCTURE OMISSION - 065-0501				
STA 764+39.00 TO STA 784+49.53		CENTERLINE	AMBER			26
STA 33+22.93 TO STA 263+11.04		CENTERLINE	AMBER			288
STA 263+14.42 TO STA 270+00.00		CENTERLINE	AMBER			9
IL 29 AT INTERSECTION						
STA 270+00.00 TO STA 276+90.00		CENTERLINE	AMBER			32
STA 276+90.00 TO STA 287+33.48		CENTERLINE	AMBER			28
IL 10 AT INTERSECTION						
STA 0+00.00 TO STA 11+18.00		CENTERLINE	AMBER			21
STA 0+00.00 TO STA 6+47.38		CENTERLINE	AMBER			22
MASON COUNTY TOTAL						426
		PROJECT TOTAL				449

SHORT TERM PAVEMENT MARKING, 5''				CENTERLINE LENGTH (FOOT)	EDGE LINE LENGTH (FOOT)	TOTAL (FOOT)
IL 29 (MENARD COUNTY)						
STA 732+15.94 TO STA 732+50.94		3.5	2.8			
STA 732+49.96 TO STA 750+37.00		178.7	143			
MENARD COUNTY TOTAL		182.2	145.8			328
IL 29 (MASON COUNTY)						
STA 750+37.00 TO STA 764+39.00				STRUCTURE OMISSION - 065-0501		
STA 764+39.00 TO STA 784+49.53		201.1	160.8			
STA 33+22.93 TO STA 263+11.04		2298.8	1839			
STA 263+14.42 TO STA 274+00.00		108.6	86.8			
STA 274+00.00 TO STA 276+00.00		20	16			
STA 276+00.00 TO STA 277+50.00		15				
STA 277+50.00 TO STA 279+50.00		20	16			
STA 279+50.00 TO STA 287+33.48		78.3	62.6			
IL 10 (MASON COUNTY)						
STA 0+00.00 TO STA 11+18.00		111.8	89.4			
STA 0+00.00 TO STA 6+47.38		64.7	51.8			
MASON COUNTY TOTAL		2918.3	2322.4			5240.7
PROJECT TOTAL						5568.7

URETHANE PAVEMENT MARKING - LINE 5''				LENGTH (FEET)
IL 29				
STA 270+00.00 TO STA 276+90.00				4360.0
STA 276+90.00 TO STA 287+33.48				3270.0
IL 10				
STA 0+00.00 TO STA 11+18.00				3799.0
STA 0+00.00 TO STA 6+47.38				3000.0
MASON COUNTY TOTAL				14429.0

URETHANE PAVEMENT MARKING - LINE 8''				LENGTH (FEET)
IL 29				
STA 270+00.00 TO STA 276+90.00				210.0
STA 276+90.00 TO STA 287+33.48				204.0
IL 10				
STA 0+00.00 TO STA 11+18.00				0.0
STA 0+00.00 TO STA 6+47.38				0.0
MASON COUNTY TOTAL				414.0

URETHANE PAVEMENT MARKING - LINE 12''				LENGTH (FEET)
IL 29				
STA 270+00.00 TO STA 276+90.00				213.0
STA 276+90.00 TO STA 287+33.48				213.0
IL 10				
STA 0+00.00 TO STA 11+18.00				0.0
STA 0+00.00 TO STA 6+47.38				0.0
MASON COUNTY TOTAL				426.0

PERFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 24''				LENGTH (FEET)
IL 29				
STA 270+00.00 TO STA 276+90.00				20.0
STA 276+90.00 TO STA 287+33.48				16.0
IL 10				
STA 0+00.00 TO STA 11+18.00				32.0
STA 0+00.00 TO STA 6+47.38				32.0
MASON COUNTY TOTAL				100.0

* - ((E)RS-4, (G)RS-6) I & (F)RS-3, I-1
 ** - MENARD, MASON

FILE NAME =	USER NAME = sparksgw	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwork\pwork\sparksgw\0283522\06xxxxx\sh-t-schedule.dgn		DRAWN -	REVISED -					658	*	**	106	22
PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -			CONTRACT NO. 72F04							
PLOT DATE = Feb-27-2012 02:04:32PM	DATE -	REVISED -			SCALE:	SHEET 2 OF 5 SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT			