

PAVEMENT MARKING SCHEDULE

LOCATION					WORK ZONE PAVEMENT MARKING REMOVAL	POLYUREA PAVEMENT MARKING TYPE II - LINE 4"	REPLACEMENT REFLECTOR	PAVEMENT MARKING REMOVAL	RAISED REFLECTIVE PAVEMENT MARKER, REFLECTOR REMOVAL
STATION	OFFSET	TO	STATION	OFFSET	SQ FT	FOOT	EACH	SQ FT	EACH
STAGE 1									
453+84	LT 32.0'	TO	459+39	LT 32.0'	185	555	-	185	-
453+84	LT 44.0'	TO	474+39	LT 56.0'	685	-	-	-	-
464+39	LT 44.0'	TO	474+39	LT 44.0'	-	-	25	-	-
STAGE 2									
453+84	LT 56.0'	TO	459+39	LT 56.0'	185	555	-	185	-
453+84	LT 44.0'	TO	474+39	LT 32.0'	685	-	-	-	-
464+39	LT 44.0'	TO	474+39	LT 44.0'	-	-	-	-	25
TOTAL:					1740	1110	25	370	25

SHOULDER SCHEDULE

LOCATION				WIDTH	PAVED SHOULDER REMOVAL	PCC BASE COURSE WIDENING 10"	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N105	BITUMINOUS MATERIALS (PRIME COAT)
STATION	TO	STATION	LANE	FT	SQ YD	SQ YD	SQ YD	TON	GAL
453+84	TO	454+76	DRIVING	4	41	41	-	-	-
454+76	TO	455+60	DRIVING	4	-	-	37	5	4
457+17	TO	459+39	DRIVING	4	-	-	99	14	10
453+84	TO	454+74	PASSING	6	60	60	-	-	-
454+74	TO	455+56	PASSING	6	-	-	55	8	5
457+15	TO	459+39	PASSING	6	-	-	149	21	15
TOTAL:					101	101	340	48	34