

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1-57 840+69.50 TO 841+64.63 STA. EQ. 841+64.63 BK= 813+20.49 AH TO 900+52.80	1-57 900+52.80 TO 1390+20.87
				URBAN 0005	RURAL 0005
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	47600	5459	42141
40600300	AGGREGATE (PRIME COAT)	TON	952	84	868
40600895	CONSTRUCTING TEST STRIP	EACH	2	1	1
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	8999	3333	5666
40600990	TEMPORARY RAMP	SO YD	943	355	588
40603245	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N105	TON	27017	4127	22890
40603550	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N105	TON	23480	2751	20729
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	65		65
44201777	CLASS D PATCHES, TYPE II, 11 INCH	SO YD	1862	218	1644
44201781	CLASS D PATCHES, TYPE III, 11 INCH	SO YD	1862	218	1644
44201783	CLASS D PATCHES, TYPE IV, 11 INCH	SO YD	1862	218	1644
48101200	AGGREGATE SHOULDERS, TYPE B	TON	5644	661	4983

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1-57 840+69.50 TO 841+64.63 STA. EQ. 841+64.63 BK= 813+20.49 AH TO 900+52.80	1-57 900+52.80 TO 1390+20.87
				URBAN 0005	RURAL 0005
48203100	HOT-MIX ASPHALT SHOULDERS	TON	31299	4798	26501
63100169	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED	EACH	1		1
63200310	GUARDRAIL REMOVAL	FOOT	50		50
63301210	REMOVE AND REERECT STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	6987.5	1862.5	5125
63302000	REMOVE AND REERECT TRAFFIC BARRIER TERMINALS, TYPE 2	EACH	17	4	13
63302700	REMOVE AND REERECT TRAFFIC BARRIER TERMINALS, TYPE 6	EACH	4		4
63302710	REMOVE AND REERECT TRAFFIC BARRIER TERMINALS, TYPE 6A	EACH	7	4	3
63303720	REMOVE AND REERECT TRAFFIC BARRIER TERMINALS, TYPE 6B	EACH	8	2	6
64200116	SHOULDER RUMBLE STRIPS, 16 INCH	FOOT	209520	24563	184957
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	2	4

FILE NAME =	USER NAME = swartzw	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES		F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwwork\pwwid\swartzw\d0288358\077560-ah-sec.dgn	PLOT SCALE = 100.0000' / 1"	DRAWN -	REVISED -				57	.	Coles	48	4
	PLOT DATE = 1/31/2012	CHECKED -	REVISED -		SCALE: NA SHEET 1 OF 3 SHEETS STA. TO STA.		ILLINOIS FED. AID PROJECT		CONTRACT NO. 74560		
		DATE -	REVISED -								