

PAVING SCHEDULE		LENGTH	PAVEMENT WIDTH	AREA	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	POLYMERIZED HOT MIX ASPHALT SURFACE COURSE, MIX "D", N105	POLYMERIZED HOT MIX ASPHALT BINDER COURSE, IL-19.0, N105	HOT-MIX ASPHALT SURFACE REMOVAL (BUTT-JOINT)	TEMPORARY RAMP	HOT MIX ASPHALT SHOULDERS	SHOULDER RUMBLE STRIPS, 16"	AGGREGATE SHOULDERS, TYPE B	INCIDENTAL HOT-MIX ASPHALT SURFACING
STATION	TO STATION	FEET	FEET	SQ YD	GALLON	TON	TON	TON	SQ YD	SQ YD	TON	FOOT	TON	TON
840+69.50	TO 841+44.50	75.0	48.0	400.0	66.7	1.3	33.6	50.4	666.7	88.8	56.0	300.0	8.1	
841+44.50	TO 841+64.63	20.1	48.0	107.4	17.9	0.4	9.0	13.5			15.0	80.5	2.2	
841+64.63	= 813+20.49	Sta. Eq.	NA	0.0	0.0	0.0	0.0	0.0			0.0	Sta. Eq.	0.0	
813+20.49	TO 846+44.94	3,324.5	48.0	17,730.4	2,955.1	59.1	1,489.4	2,234.0			2,482.3	13,297.8	357.6	
846+44.94	TO 847+15.00	70.1	48.0	373.7	62.3	1.2	31.4	47.1			52.3	280.2	7.5	
847+15.00	TO 848+85.00	170.0	48.0	906.7	151.1	3.0	76.2	114.2			126.9	680.0	18.3	
848+85.00	TO 849+54.95	69.9	48.0	373.1	62.2	1.2	31.3	47.0			52.2	279.8	7.5	
849+54.95	TO 854+84.14	529.2	48.0	2,822.3	470.4	9.4	237.1	355.6			395.1	2,116.8	56.9	
854+84.14	TO 856+64.14	180.0	48.0	960.0	160.0	3.2	80.6	121.0	1,200.0	88.8	134.4	720.0	19.4	
856+64.14	TO 857+81.80	117.3	NA	0.0	0.0	0.0	0.0	0.0			0.0	0.0	0.0	
857+81.80	TO 859+61.80	180.0	48.0	960.0	160.0	3.2	80.6	121.0	1,200.0	88.8	134.4	720.0	19.4	
859+61.80	TO 870+95.20	1,133.4	48.0	6,044.8	1,007.5	20.1	507.8	761.6			846.3	4,533.6	121.9	
870+95.20	TO 871+25.20	30.0	48.0	160.0	26.7	0.5	13.4	20.2	133.3	44.4	22.4	120.0	3.2	
871+25.20	TO 878+12.10	686.9	24.0	1,831.7	305.3	6.1	153.9	230.8			256.4	1,373.8	36.9	
878+12.10	TO 878+42.10	30.0	24.0	80.0	13.3	0.3	6.7	10.1	133.3	44.4	11.2	60.0	1.6	
878+42.10	TO 900+52.80	2,211.6	NA	0.0	0.0	0.0	0.0	0.0			0.0	0.0	0.0	
900+52.80	TO 923+41.35	2,288.6	NA	0.0	0.0	0.0	0.0	0.0			0.0	0.0	0.0	
923+41.35	TO 923+71.35	30.0	24.0	80.0	13.3	0.3	6.7	10.1	133.3	44.4	11.2	60.0	1.6	
923+71.35	TO 927+35.50	364.4	24.0	971.7	161.9	3.2	81.6	122.4			136.0	728.7	19.6	
927+35.50	TO 927+65.50	30.0	48.0	160.0	26.7	0.5	13.4	20.2	133.3	44.4	22.4	120.0	3.2	
927+65.50	TO 1055+43.99	12,778.5	48.0	68,151.9	11,374.5	227.5	5,724.8	8,587.1			9,541.3	51,114.0	1,377.7	*33.2
1055+43.99	TO 1056+13.99	70.0	48.0	373.3	62.2	1.2	31.4	47.0			52.3	280.0	7.5	
1056+13.99	TO 1057+86.00	172.0	48.0	917.4	152.9	3.1	77.1	115.6			128.4	688.0	18.5	
1057+86.00	TO 1058+56.00	70.0	48.0	373.3	62.2	1.2	31.4	47.0			52.3	280.0	7.5	
1058+56.00	TO 1115+85.09	5,729.1	48.0	30,555.1	5,092.5	101.9	2,566.6	3,849.9			4,277.7	22,916.4	617.7	
1115+85.09	TO 1116+55.00	69.9	48.0	372.9	62.1	1.2	31.3	47.0			52.2	279.6	7.5	
1116+55.00	TO 1116+70.00	15.0	48.0	80.0	13.3	0.3	6.7	10.1			11.2	60.0	1.6	
1116+70.00	TO 1117+40.00	70.0	48.0	373.3	62.2	1.2	31.4	47.0			52.3	280.0	7.5	
1117+40.00	TO 1118+70.00	130.0	48.0	693.3	115.6	2.3	58.2	87.4			97.1	520.0	14.0	
1118+70.00	TO 1119+40.00	70.0	48.0	373.3	62.2	1.2	31.4	47.0			52.3	280.0	7.5	
1119+40.00	TO 1119+60.00	20.0	48.0	106.7	17.8	0.4	9.0	13.4			14.9	80.0	2.2	
1119+60.00	TO 1120+30.00	70.0	48.0	373.3	62.2	1.2	31.4	47.0			52.3	280.0	7.5	
1120+30.00	TO 1133+17.92	1,287.9	48.0	6,868.9	1,144.8	22.9	577.0	865.5			961.6	5,151.7	138.9	
1133+17.92	TO 1133+58.00	40.1	48.0	213.8	35.6	0.7	18.0	26.9			29.9	160.3	4.3	
1133+58.00	TO 1133+88.00	30.0	48.0	160.0	26.7	0.5	13.4	20.2			22.4	120.0	3.2	
1133+88.00	TO 1134+28.01	40.0	48.0	213.4	35.6	0.7	17.9	26.9			29.9	160.0	4.3	
1134+28.01	TO 1140+58.00	630.0	48.0	3,359.9	560.0	11.2	282.2	423.4			470.4	2,520.0	67.9	
1140+58.00	TO 1140+98.00	40.0	48.0	213.3	35.6	0.7	17.9	26.9			29.9	160.0	4.3	
1140+98.00	TO 1141+27.84	29.8	48.0	159.1	26.5	0.5	13.4	20.1			22.3	119.4	3.2	
SHEET TOTALS		32,093		147,894	24,665	493	12,423	18,635	3,600	444	20,705	110,921	2,988	33

*MEDIAN CROSS-OVER STA. 1024+52.85

FILE NAME =	USER NAME = swartzw	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ca:\pw_work\pwwork\swartzw\10288358\077	560-shr-sch.dgn	DRAWN -	REVISED -		SCALE: NA	SHEET 1	OF 6 SHEETS	STA.	TO STA.	57	Coles	48	13
	PLOT SCALE = 50.0000' / 1" =	CHECKED -	REVISED -						ILLINOIS FED. AID PROJECT				
	PLOT DATE = 1/31/2012	DATE -	REVISED -						CONTRACT NO. 74560				