

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		80% FED. 20% STATE 0005		
*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	140	140		
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	26	26		
*78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4		
X2020110	GRADING AND SHAPING SHOULDERS	UNIT	2.6	2.6		
*X2501000	SEEDING, CLASS 2 (SPECIAL)	ACRE	0.15	0.15		
*X6311217	TRAFFIC BARRIER TERMINAL, TYPE 6B (SPECIAL)	EACH	2	2		
Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO 50 FT OR LESS THAN 5 INCHES)		43	43		
Z0049799	PROTECTING OR RESETTING SURVEY MARKERS	EACH	2	2		
Z0070202	SURVEY MARKER VAULT	EACH	2	2		

*SPECIALTY ITEM

FILE NAME =	USER NAME = staffennk	DESIGNED -	REVISED -
c:\pwork\pwork\stffennk\0289124\074566-sht-soq.dgn		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES	
SCALE: NA	SHEET 3 OF 3 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
828	I2RS-1	Effingham	37	6
ILLINOIS FED. AID PROJECT			CONTRACT NO. 74566	