

PAVING SCHEDULE

| F. A. P. RT. 828 | | | LENGTH | PAVEMENT WIDTH | AREA | AGGREGATE SHOULDERS, TYPE B | BITUMINOUS MATERIALS (PRIME COAT) | AGGREGATE (PRIME COAT) | HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2" | POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90 |
|------------------|----|-----------|--------|----------------|---------|-----------------------------|-----------------------------------|------------------------|---|--|
| STATION | TO | STATION | FEET | FEET | SQ YD | TON | GALLON | TON | SQ. YD. | TON |
| 486+13.00 | TO | 488+47.00 | 234.0 | 22.0 | 572.0 | 3.3 | 68.9 | 1.4 | 689.0 | 57.9 |
| 488+47.00 | TO | 490+16.00 | 169.0 | 22.0 | 413.1 | 0.0 | 58.2 | 1.7 | 582.1 | 48.9 |
| 490+16.00 | TO | 494+96.00 | 480.0 | 22.0 | 1,173.3 | 6.8 | 117.3 | 4.1 | 1173.3 | 119.8 |
| 494+96.00 | TO | 498+68.00 | 372.0 | 22.0 | 909.3 | 0.0 | 128.1 | 5.1 | 1281.3 | 107.6 |
| 498+68.00 | TO | 501+32.00 | 264.0 | 22.0 | 645.3 | 10.0 | 90.9 | 4.1 | 909.3 | 76.4 |
| 501+32.00 | TO | 507+25.00 | 593.0 | 22.0 | 1,449.6 | 16.9 | 145.0 | 7.2 | 1449.6 | 121.8 |
| TOTALS | | | 1,255 | | 5,163 | 37 | 608 | 24 | 6,085 | 532 |

PAVEMENT MARKING SCHEDULE

| F. A. P. RT. 828 | | | LENGTH | SHORT TERM PAVEMENT MARKINGS | WORK ZONE PAVEMENT MARKING REMOVAL | THERMOPLASTIC PAVEMENT MARKING-LINE 4" | RAISED REFLECTIVE PAVEMENT MARKERS | THERMOPLASTIC PAVEMENT MARKING - LINE 24" |
|------------------|----|-----------|--------|------------------------------|------------------------------------|--|------------------------------------|---|
| STATION | TO | STATION | FOOT | FOOT | SO FT | FOOT | EACH | FOOT |
| 486+13.00 | TO | 488+47.00 | 234.0 | 46.8 | 7.8 | 459.5 | 2.9 | |
| 488+47.00 | TO | 490+16.00 | 169.0 | 33.8 | 5.6 | 114.3 | 2.1 | 60.0 |
| 490+16.00 | TO | 494+96.00 | 480.0 | 96.0 | 16.0 | 1,080.0 | 6.0 | 60.0 |
| 494+96.00 | TO | 498+68.00 | 372.0 | 74.4 | 12.4 | 560.0 | 4.7 | |
| 498+68.00 | TO | 501+32.00 | 264.0 | 52.8 | 8.8 | 534.0 | 3.3 | |
| 501+32.00 | TO | 507+25.00 | 593.0 | 118.6 | 19.8 | 1,216.3 | 7.4 | 20.0 |
| SHEET TOTALS | | | 2,112 | 422 | 70 | 3,964 | 26 | 140 |

COMBINATION CURB AND GUTTER REMOVAL

| LOCATION | QUANTITY (FT) | DESC. |
|----------------------------|---------------|-------|
| F. A. P. RT. 828 | | |
| 490+97.00 TO 494+50.20 LT. | 355.0 | B6.12 |
| PROJECT TOTAL | | 355.0 |

PORTLAND CEMENT CONCRETE SIDEWALK 4"

| LOCATION | QUANTITY (SQ. FT.) | |
|----------------------------|--------------------|---------|
| F. A. P. RT. 828 | | |
| 490+95.50 TO 491+84.70 LT. | 361.0 | |
| 492+24.40 TO 494+50.20 LT. | 1,005.0 | |
| PROJECT TOTAL = | | 1,366.0 |

COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12

| LOCATION | QUANTITY (FT) | |
|----------------------------|---------------|-------|
| F. A. P. RTE. 828 | | |
| 490+97.00 TO 494+50.20 LT. | 355.0 | |
| PROJECT TOTAL | | 355.0 |

SIDEWALK REMOVAL

| LOCATION | QUANTITY (SQ. FT.) | |
|----------------------------|--------------------|---------|
| F. A. P. RT. 828 | | |
| 490+95.50 TO 491+84.70 LT. | 361.0 | |
| 492+24.40 TO 494+50.20 LT. | 1,005.0 | |
| PROJECT TOTAL | | 1,366.0 |