

SHOULDER & PAVEMENT SCHEDULE

LOCATION	PAVEMENT REMOVAL	HMA SURFACE REMOVAL, 3/4"	HMA SURFACE REMOVAL - BUTT JOINT	PAVED SHOULDER REMOVAL	AGGREGATE BASE COURSE, TYPE A 12"	HMA BASE COURSE WIDENING, 6" (STAGE IA)	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	HMA PAVEMENT (FULL DEPTH), 11"	LEVELING BINDER (MACHINE METHOD), N70	HMA BINDER COURSE, IL-19.0 FG, N70	HMA SURFACE COURSE, MIX "D", N70	HMA SHOULDERS, 8"	HMA BASE COURSE, 9"	AGGREGATE SHOULDERS, TYPE A 6"	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	STRIP REFLECTIVE CRACK CONTROL TREATMENT
STATION TO STATION	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	TON	TON	TON	SQ YD	TON	TON	TON	SQ YD	SQ YD	SQ YD	FOOT	FOOT
IL 157																	
STA 49+28.53 TO STA 50+00.00	4.2	190.5	40	0.6			0.06	0.33		11.1		16.1	63.5				142.9
STA 50+00.00 TO STA 51+00.00	49.7	266.7		69.3			0.09	0.44		19.6		22.4	88.9				200
STA 51+00.00 TO STA 52+00.00		266.7		27.1			0.09	0.44		19.6		22.4	88.9				200
STA 52+00.00 TO STA 53+00.00		266.7					0.09	0.44		19.6		22.4	88.9				200
STA 53+00.00 TO STA 54+00.00		266.7					0.09	0.44		19.6		22.4	88.9				200
STA 54+00.00 TO STA 55+00.00		266.7					0.09	0.44		19.6		22.4	32.7	112.4			200
STA 55+00.00 TO STA 56+00.00		266.7					0.09	0.44		19.6		22.4		177.8			200
STA 56+00.00 TO STA 57+00.00		30.1					0.02	0.09		2.2		3.9		30.6		28.5	200
STA 57+00.00 TO STA 58+00.00		115.9					0.06	0.24		13.6		11.2		88.0		28.5	200
STA 58+00.00 TO STA 59+00.00		266.7					0.09	0.44		31.4		22.4	47.3	83.2			200
STA 59+00.00 TO STA 60+00.00		266.7					0.09	0.44		31.4		22.4	88.9				200
STA 60+00.00 TO STA 61+00.00		266.7					0.09	0.44		31.4		22.4	88.9				200
STA 61+00.00 TO STA 62+00.00		266.7					0.09	0.44		31.4		22.4	88.9				200
STA 62+00.00 TO STA 63+00.00	67.5	200			69.5		0.03	0.44		7.8	35.5	22.4	88.9				50
STA 63+00.00 TO STA 64+00.00	270				277.8			0.44			142.0	22.4	88.9				
STA 64+00.00 TO STA 65+00.00	67.5	200			69.5		0.03	0.44		4.1	35.5	22.4	88.9				50
STA 65+00.00 TO STA 66+00.00		266.7					0.09	0.44		16.4		22.4	88.9				200
STA 66+00.00 TO STA 67+00.00		266.7					0.09	0.44		4.1		22.4	88.9				200
STA 67+00.00 TO STA 68+00.00		266.7					0.09	0.44		16.4		22.4	88.9				200
STA 68+00.00 TO STA 68+30.58		81.4	40				0.03	0.17		0.1		6.9	27.1				61.1
OLD CARPENTER ROAD	1513.1																
STA 0+12.47 TO STA 1+00.00					223.7				195.5				71.3				
STA 1+00.00 TO STA 2+00.00					255.6				244.4				88.9				
STA 2+00.00 TO STA 3+00.00					255.6				244.4				88.9				
STA 3+00.00 TO STA 4+00.00					255.6	35.6			244.4				88.9				
STA 4+00.00 TO STA 5+00.00					255.6	44.6			244.4				88.9				
STA 5+00.00 TO STA 5+51.49					131.6	20.1			125.9				45.8				
STA 5+51.49 TO STA 6+00.00						21.7											
SERVICE DRIVE																	
STA 10+12.00 TO STA 11+00.00					244.5							37.7			36.4		
STA 11+00.00 TO STA 12+00.00					277.8							44.8			44.4		
STA 12+00.00 TO STA 13+00.00					277.8							44.8			44.5		
STA 13+00.00 TO STA 14+00.00					277.8							44.8			44.5		
STA 14+00.00 TO STA 14+79.39					51.6			0.13				8.4			8.2		
TOTAL	1972	4285	80	97	2924	122	1.4	8	1299	319	213	577	1799	492	178	57	3304