

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		90% FED 10% STATE 0021	SUMMARY OF QUANTITIES			TOTAL QUANTITIES	90% FED 10% STATE 0021	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		CODE NO	ITEM		UNIT	CODE NO	ITEM			UNIT	
20200600	EXCAVATING AND GRADING EXISTING SHOULDER	UNIT	158.4	158.4		* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	15840	15840			
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	1.7	1.7									
40600300	AGGREGATE (PRIME COAT)	TON	8	8									
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	751	751									
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	5280	5280									
64200108	SHOULDER RUMBLE STRIPS, 8 INCH	FOOT	15840	15840									
67100100	MOBILIZATION	L SUM	1	1									
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1									
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	5	5									
70300100	SHORT TERM PAVEMENT MARKING	FOOT	633.6	633.6									
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	15840	15840									
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	5280	5280									

* SPECIALTY ITEM

FILE NAME =	USER NAME = millerj	DESIGNED -	REVISED -
er\pwwork\pindot\millerj\d0277225\d876f17-aht-plan.dgn		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 / in.	CHECKED -	REVISED -
	PLOT DATE = 2/3/2012	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: NTS SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
817	6-1	WASHINGTON	7	3
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 76F17	