



**DETAIL
CCTV CAMERA AND RADAR VEHICLE DETECTOR**

NOT TO SCALE

LOCATIONS:

ITS ELEMENTS SCHEDULE					
CAMERA	STA.	EOP OFFSET	RADAR DETECTION	STA.	EOP OFFSET
(1) 027009.0A. C	184+86 LT (NB *)	5' BHGR	(2)027009.0A.76D	571+45 RT (EB)	35'
			(1)027009.9A.77D	618+80 RT (EB)	30'
			(1)027010.8A.78D	667+50 RT (EB)	30'
			(1)027012.0A.79D	716+20 RT (EB)	35'
			(1)027012.6A.80D	758+00 RT (EB)	30'
			(1)027013.3A.81D	794+00 RT (EB)	20'
			(1)027015.0A.82D	857+50 RT (EB)	20'
			(1)007015.4A.83D	961+00 LT (WB)	25'
			(1)007016.1A.63D	1002+60 RT (EB)	30'
			(1)007016.8A.65D	1036+00 RT (EB)	30'

*=IL 157 (1)=LIGHT POLE, STEEL 50 FT. WITH CAMERA LOWERING SYSTEM
BGR=BEHIND GUARDRAIL (2)=LIGHT POLE, GALVANIZED STEEL, 30 FT. M.H., TENON MOUNT

CAMERAS WILL BE INSTALL IN FUTURE BY OTHERS

FILE NAME =	USER NAME = prestonme	DESIGNED -	REVISED -
et:\pw\work\p\dot\prestonme\d0279896\d076f22-sht-ITS.dgn		DRAWN -	REVISED -
	PLOT SCALE = 100.0000' / 1in.	CHECKED -	REVISED -
	PLOT DATE = 2/2/2012	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

RADAR VEHICLE DETECTION DETAIL

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
270/70	DIST 8 ITS 2012-1	MADISON	8	8
CONTRACT NO. 76F22				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				