

REMOVAL SCHEDULE

LOCATION STATION	PAVEMENT REMOVAL	HMA SURFACE REMOVAL - BUTT JOINT	PAVE SHOULDER REMOVAL	GUARDRAIL REMOVAL
IL 146 (FAP 885)	SQ YD	SQ YD	SQ YD	FOOT
<b>EAST</b>				
STA 1256+27 RT TO STA 1258+10 RT			82	
STA 1256+49 LT TO STA 1258+10 LT			72	
STA 1256+87 TO STA 1257+17		107		
STA 1257+43.28 TO STA 1257+86.40				86
STA 1257+68 TO STA 1258+10	155			
1258+10 TO STA 1258+50	147			
STA 1260+00 TO STA 1260+40				
<b>WEST</b>				
STA 1260+00 TO STA 1260+40	146			
STA 1260+19.08 LT TO STA 1262+42.28 LT				223
STA 1260+19.08 RT TO 1260+78.72 RT				60
STA 1260+26 TO STA 1262+55			238	
STA 1262+70 TO 1263+00		107		
<b>TOTALS</b>	<b>448</b>	<b>214</b>	<b>392</b>	<b>369</b>

HOT-MIX ASPHALT SCHEDULE

LOCATION STATION	HMA LEVELING BINDER (MACHINE METHOD), N90	HMA SURFACE COURSE MIX "C", N90	BITUMINOUS MATERIALS (PRIME COAT)
IL 146 (FAP 885)	TON	TON	GALLON
<b>EAST</b>			
STA 1256+87 TO STA 1257+67		24	
STA 1257+27 TO STA 1257+67	12		23
			12
<b>WEST</b>			
STA 1260+40 TO STA 1262+55		53	62
STA 1260+40 TO STA 1262+65	53		65
STA 1262+55 TO STA 1263+00		14	13
<b>TOTALS</b>	<b>65</b>	<b>91</b>	<b>175</b>

SHOULDER SCHEDULE

LOCATION STATION	HMA SHOULDERS, 8"	HMA BASE COURSE WIDENING, 10"	HMA SHOULDERS, 10"
IL 146 (FAP 885)	SQ YD	SQ YD	SQ YD
<b>NW QUAD</b>			
STA 1260+26 TO 1261+92		55	
STA 1261+27.23 TO STA 1263+00	146		
<b>NE QUAD</b>			
STA 1256+27.42 TO STA 1257+86.40	66		
STA 1256+27 TO STA 1258+10		61	
<b>SW QUAD</b>			
STA 1260+19.08 TO STA 1261+64.06			106
STA 1261+64.06 TO STA 1263+00	88		
<b>SE QUAD</b>			
STA 1256+48 TO STA 1257+86.40			62
<b>TOTALS</b>	<b>300</b>	<b>116</b>	<b>168</b>

EROSION CONTROL SCHEDULE

LOCATION STATION	PERIMETER EROSION BARRIER	EROSION CONTROL BLANKET	TEMPORARY DITCH CHECKS
IL 146 (FAP 885)	FOOT	SQ YD	FOOT
<b>NW QUAD</b>			
STA 1259+32 TO STA 1259+37		21	
STA 1259+37 TO STA 1263+00	370		
STA 1259+99.25 TO STA 1260+30.78		21	
STA 1260+16			4
<b>SW QUAD</b>			
STA 1259+32 TO STA 1259+37		14	
STA 1259+37 TO STA 1263+00	369		
STA 1259+83 TO STA 1260+12		48	
STA 1260+36 TO STA 1260+71		24	
STA 1260+53			4
<b>NE QUAD</b>			
STA 1257+00 TO STA 1258+67	210		
STA 1258+92 TO STA 1258+97		38	
<b>SE QUAD</b>			
STA 1257+00 TO STA 1258+67	208		
STA 1257+25 TO STA 1257+75		142	
STA 1258+92 TO STA 1258+97		37	
<b>TOTALS</b>	<b>1157</b>	<b>345</b>	<b>8</b>

FILE NAME = c:\pwworkspace\lenderbo\021042\78168-11t-cover.dgn

USER NAME = \$USER\$	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = 100.0000' / 1"	CHECKED -	REVISED -
PLOT DATE = 2/2/2012	DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES			
SCALE:	SHEET NO.	OF SHEETS	STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
885	6B-2	POPE	51	10
CONTRACT NO. 78168			ILLINOIS FED. AID PROJECT	