

PAVEMENT AND REMOVAL SCHEDULE

LOCATION STATION TO STATION	PORTLAND CEMENT CONCRETE PAVEMENT, 9 1/2" (JOINTED)	SUB BASE GRANULAR MATERIAL, TYPE A, 12"	PROTECTIVE COAT	HOT-MIX ASPHALT SHOULDERS, 8"	PAVEMENT REMOVAL	AGGREGATE SURFACE COURSE, TYPE B	COMB. CURB AND GUTTER REMOVAL	ISLAND REMOVAL	MEDIAN REMOVAL
	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	TON	FOOT	SQ FT	SQ FT
STAGE 1									
STA 386+43(IL 149) TO STA 386+57(IL 149)		16		16				140	
STAGE 2									
STA 383+97(IL 3) TO STA 396+17(IL 3)	2630	2840	2630	815	2585				
STA 384+10(IL 3) TO STA 386+80(IL 3)									3360
STA 387+00(IL 3) - FIELD ENTRANCE LT						7			
STAGE 3									
STA 383+60(IL 149) TO STA 386+48(IL 149)									4265
STA 384+16(IL 3) TO STA 387+21(IL 3)	1240	1300	1240		1235				
STA 384+16(IL 3) TO STA 383+69(IL 149)				350					
STA 386+29(IL 3) TO STA 385+94(IL 149)							95		
STAGE 4									
STA 387+21(IL 3) TO STA 396+17(IL 3)	2250	2420	2250		2250				
STA 383+60(IL 149) TO STA 396+17(IL 3)				770					
STA 385+62(IL 149) TO STA 388+22(IL 3)							140		
TOTALS	6,120	6,576	6,120	1,951	6,070	7	235	140	7,625