

SUMMARY OF QUANTITIES

CONSTRUCTION TYPE CODE: 0028

CODE NUMBER	PAY ITEMS	UNIT	TOTAL QUANTITY
20200100	EARTH EXCAVATION	CU YD	48.8
20400800	FURNISHED EXCAVATION	CU YD	319.9
20800150	TRENCH BACKFILL	CU YD	6.4
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	3894.5
25000300	SEEDING, CLASS 3	ACRE	1.46
25100115	MULCH, METHOD 2	ACRE	1.46
25100630	EROSION CONTROL BLANKET	SQ YD	2251.1
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	439.0
28000305	TEMPORARY DITCH CHECKS	FOOT	30.0
28000400	PERIMETER EROSION BARRIER	FOOT	1509.2
28000500	INLET AND PIPE PROTECTION	EACH	3.0
35101400	AGGREGATE BASE COURSE, TYPE B	TON	1391.8
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	153.1
40603000	HOT-MIX ASPHALT BINDER COURSE, IL-12.5, N50	TON	58.8
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	1235.3
42400300	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH	SQ FT	84.0
42400800	DETECTABLE WARNINGS	SQ FT	40.0
54215545	METAL END SECTIONS 10"	EACH	3.0
550B0040	STORM SEWERS, CLASS B, TYPE 1, 10"	FOOT	114.0
60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	3.0
* 66400105	CHAIN LINK FENCE, 4'	FOOT	1150.0

DATE	BY	SURVEY	PLOTTED	TEMPLATE	AREAS	CHECKED
		FINAL				
		SURVEY				
		NOTE BOOK				
		NO.				

DATE	BY	SURVEY	PLOTTED	TEMPLATE	AREAS	CHECKED
		ORIGINAL				
		SURVEY				
		NOTE BOOK				
		NO.				

FILE NAME =	USER NAME =	DESIGNED --	REVISED --
		DRAWN -- MPK	REVISED --
		CHECKED -- MKM	REVISED --
		DATE -- 2.14.12	REVISED --

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES	
SCALE:	SHEET NO. 1 OF 2 SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	10-00043-00-BT	ROCK ISLAND	31	2
CONTRACT NO. 85556				
ILLINOIS FED. AID PROJECT				