



EROSION CONTROL NOTES

The soil erosion and sediment control practices will be inspected weekly and after 1/2" of rain or more by the individual on site in charge of soil erosion and sediment control during the construction of the project.

Perimeter erosion barrier shall comply with Section 280 of the Standard Specifications and shall be placed as shown on this Erosion Control Plan and in accordance with stations shown on the Schedule of Quantities sheet or as directed by the Engineer.

Silt fence shall be installed following the completion and stabilization of all areas adjacent to the on-site drainages. the silt fence will remain in place until the contributing area is stabilized.

For Seeding, Class 2 (Special) see Special Provisions.

Erosion control blanket shall be placed on all disturbed areas as shown on this Erosion Control Plan sheet and in accordance with Section 251 of the Standard Specifications for Road and Bridge Construction.

The use of green dye in the erosion control blanket is not acceptable.

Stockpiles of soil and other building materials to remain in place more than 3 days shall be furnished with erosion and sediment control measures (i.e. perimeter silt fence). Stockpiles to remain in place for 14 days or more shall receive temporary seeding.

All adjacent streets must be kept clear of debris. Inspected daily and cleaned when necessary.

LEGEND



- Perimeter Erosion Barrier
- Seeding, Class 2 (Special)
- Erosion Control Blanket

BILL OF MATERIAL

Item	Unit	Quantity
Erosion Control Blanket	Sq. Yd.	1,560
Temporary Erosion Control Seeding	Pound	32
Perimeter Erosion Barrier	Foot	671
Seeding, Class 2 (Special)	Acre	0.32

FILE: S:\PROJECTS\2011\224011.Lee.Co.DESIGN\STRUCT\Drawings\224011.Erosion.dgn



DESIGNED - BRADLEY KLEINMAIER	REVISED -
CHECKED - MEGAN CACKLEY	REVISED -
DRAWN - RON ALLEN	REVISED -
CHECKED - MICHAEL WAGNER	REVISED -

**LEE COUNTY
C.H. 12 (KEIGWIN ROAD) OVER GREEN RIVER
STATION 20+00**

**EROSION CONTROL PLAN
STRUCTURE NO. 052-3416**

SCALE: 1" = 20' SHEET NO. 1 OF 1 SHEET STA. 17+00.00 TO STA. 23+00.00

F.A.S. RTE. 1180	SECTION 11-00318-00-BR	COUNTY LEE	TOTAL SHEETS 29	SHEET NO. 7
WHA# 1224D11			CONTRACT NO. 85557	
ILLINOIS FED. AID PROJECT BRS-1180(003)				