

SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
06-00100-02-RS	LIVINGSTON	5	5

PROJECT NO. RS-1362(115)

SCHEDULE OF RESURFACING QUANTITIES

Unit weight Constant = 112.0 lbs./s.y./inch

LOCATION (QUANTITY)	LENGTH	AREA (SQ YD)	COLD MILLING (SPL) (FOOT)	SHORT- TERM PAVT MARKING (FOOT)	WORK ZONE PAVT MK REM (SQ FT)	PAINT PVT MARKING LINE, 4" (FOOT)	BIT MATLS PR CT RC-70 (GALLON)	BIT MATLS PR CT MC-30 (GALLON)	BIT MATL CIR ENG EMULSION (GALLON)	COLD IN-PLACE RECYCLING 4" DEPTH (SQ YD)	LEVEL BINDER IL-19.0 N50 (TON)	BIT CONC SURF CSE "C" N50 (TON)	INCIDENTAL BIT SURF (TON)	AGG WEDGE SHOULDERS TYPE B (TON)
<i>MAINLINE</i>														
373+60. to 375+60. (TAPER)	200	489	200	(2 Apps.) 40	(1 App.) 7	50	-	-	664	489	41	41	-	35
375+60. to 410+81.5	3522	8608	-	704	117	880	-	-	11699	8608	723	723	-	624
410+81.5 to 412+81.5 (TAPER)	200	489	200	40	7	50	-	-	664	489	41	41	-	35
412+81.5 to 427+31.5 (MILL)	1450	3544	1450	290	48	363	-	-	4817	3544	298	298	-	-
427+31.5 to 427+76.5 (053-3026)	45	110	-	10	2	11	-	-	-	-	-	-	-	-
427+76.5 to 429+76.5 (TAPER)	200	489	200	40	7	50	-	-	664	489	41	41	-	35
429+76.5 to 477+27.5	4751	11614	-	950	158	1188	-	-	15784	11614	976	976	-	842
477+27.5 to 479+27.5 (TAPER)	200	489	200	40	7	50	-	-	664	489	41	41	-	35
479+27.5 to 479+72.5 (053-3027)	45	110	-	10	2	11	-	-	-	-	-	-	-	-
479+72.5 to 481+72.5 (TAPER)	200	489	200	40	7	50	-	-	664	489	41	41	-	35
481+72.5 to 492+09.1	1037	2534	-	208	35	259	-	-	3444	2534	213	213	-	184
492+09.1 to 494+09.1 (TAPER)	200	489	200	40	7	50	-	-	664	489	41	41	-	35
494+09.1 to 494+54.1 (053-3028)	45	110	-	10	2	11	-	-	-	-	-	-	-	-
494+54.1 to 496+54.1 (TAPER)	200	489	200	40	7	50	-	-	664	489	41	41	-	35
496+54.1 to 498+53.35	199	487	-	40	7	50	-	-	662	487	41	41	-	35
498+53.35 to 500+53.35 (TAPER)	200	489	200	40	7	50	-	-	664	489	41	41	-	35
500+53.35 to 500+93.85 (053-3029)	40.5	99	-	8	1	10	-	-	-	-	-	-	-	-
500+93.85 to 502+93.85 (TAPER)	200	489	200	40	7	50	-	-	664	489	41	41	-	35
502+93.85 to 626+60.	12366	30228	-	2474	412	3092	-	-	41083	30228	2539	2539	-	2191
626+60. to 628+60. (TAPER)	200	489	200	40	7	50	-	-	664	489	41	41	-	35
TOTAL JOB LENGTH OR MAINLINE QUANTITY	25500	62333	3450	5104	854	6375	-	-	84129	61905	5200	5200	-	4226
<i>MISCELLANEOUS</i>														
PRIVATE ENTRANCES (6)	-	-	-	-	-	-	-	89.0	-	-	11	11	48.0	-
SIDEROAD INTERSECTIONS (11)	-	-	-	-	-	-	99.0	-	-	-	44	44	165.0	-
M.B.T.O.'s (6)	-	-	-	-	-	-	-	40.0	-	-	10	10	-	-
TOTALS OF MAINLINE & MISC.	25,500	62,333	3,450	5,104	854	6,375	99	129	84,129	61,905	5,265	5,265	213	4,226

I:\chd2010\ch20\work\ROAD Projects\00100RSZ-CowayRd-East\Planning\EstCost-Resurf\Sched-1-CowayRd.xls\SchedResurfQty