

SUMMARY OF QUANTITIES

CONSTRUCTION TYPE CODE: 0011

PAY CODE	QUANTITY	UNIT	ITEM
20100500	0.74	Acre	Tree Removal, Acres
20300100	637	Cu. Yd.	Channel Excavation
25100630	2,671	Sq. Yd.	Erosion Control Blanket
28000305	63	Foot	Temporary Ditch Checks
28000400	318	Foot	Perimeter Erosion Barrier
28000500	3	Each	Inlet and Pipe Protection
*40200100	780	Ton	Aggregate Surface Course, Type A
*40200800	85	Ton	Aggregate Surface Course, Type B
*50100100	1	Each	Removal of Existing Structures
50105220	189	Foot	Pipe Culvert Removal
*50300225	33.8	Cu. Yd.	Concrete Structures
50400605	1,984	Sq. Ft.	Precast Prestressed Concrete Deck Beams (33" Depth)
50800105	4,260	Pound	Reinforcement Bars
Δ50900205	168	Foot	Steel Railing, Type S1
51200957	216	Foot	Furnishing Metal Shell Piles 12" x 0.250"
51202305	216	Foot	Driving Piles
51203200	2	Each	Test Pile Metal Shells
51500100	1	Each	Name Plates
542A0220	82	Foot	Pipe Culverts, Class A, Type 1 15"
542D0217	74	Foot	Pipe Culverts, Class D, Type 1 12"
54213660	1	Each	Precast Reinforced Concrete Flared End Sections 15"
54213867	4	Each	Steel End Sections 12"
67100100	1	L. Sum	Mobilization
Z0013798	1	L. Sum	Construction Layout
*X2020410	565	Cu. Yd.	Earth Excavation (Special)
*X2070302	194	Ton	Porous Granular Embankment, Special
*X2501100	0.55	Acre	Seeding, Class 3 (Special)
*X2810210	1,178	Ton	Stone Riprap, Class A5 (Special)
*X7010216	1	L. Sum	Traffic Control and Protection, (Special)

*See B.L.R. 11310 in the contract documents for Special Provisions.

Δ Specialty Items

FILE = S:\PROJECTS\2010\1286D10 - Bureau Co. TR136\DESIGN\DRAWINGS\1286D10S\summaryofquantities.dgn



DESIGNED - MICHAEL WAGNER	REVISED -
CHECKED - BRIAN CONVERSE	REVISED -
DRAWN - MICHAEL WAGNER	REVISED -
CHECKED - MEGAN CACKLEY	REVISED -

BUREAU COUNTY
T.R. 136 (1125 E. ST.) OVER FOX CREEK
STATION 20 + 05

SUMMARY OF QUANTITIES
STRUCTURE NO. 006-4235

TWP. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
136	10-16115-00-BR	BUREAU	21	2
WHA# 1286D10		CONTRACT NO. 87498		
[ILLINOIS] FED. AID PROJECT BR05-0011(084)				