

SUMMARY OF QUANTITIES

CONSTRUCTION TYPE CODE: 0011

PAY CODE	QUANTITY	UNIT	ITEM
20201200	134	Cu. Yd.	Removal and Disposal of Unsuitable Material
20300100	630	Cu. Yd.	Channel Excavation
25100630	3,699	Sq. Yd.	Erosion Control Blanket
28000305	97	Foot	Temporary Ditch Checks
28000400	130	Foot	Perimeter Erosion Barrier
28000500	2	Each	Inlet and Pipe Protection
31100100	638	Ton	Subbase Granular Material, Type A
*31101000	320	Ton	Subbase Granular Material, Type B
*40200800	143	Ton	Aggregate Surface Course, Type B
*40600100	641	Gallon	Bituminous Materials (Prime Coat)
40603000	115	Ton	Hot-Mix Asphalt Binder Course, IL-12.5, N50
40603310	152	Ton	Hot-Mix Asphalt Surface Course, Mix "C", N50
48101200	149	Ton	Aggregate Shoulders, Type B
50100100	1	Each	Removal of Existing Structures
50105220	64	Foot	Pipe Culvert Removal
50200100	240	Cu. Yd.	Structure Excavation
50300225	38.0	Cu. Yd.	Concrete Structures
50400605	2,205	Sq. Ft.	Precast Prestressed Concrete Deck Beams (33" Depth)
50800205	4,600	Pound	Reinforcement Bars, Epoxy Coated
+50900205	150	Foot	Steel Railing, Type S1
51200957	448	Foot	Furnishing Metal Shell Piles 12" x 0.250"
51202305	448	Foot	Driving Piles
51203200	2	Each	Test Pile Metal Shells
51204650	10	Each	Pile Shoes
51500100	1	Each	Name Plates
54200220	94	Foot	Pipe Culverts, Class D, Type 1 15"
54213870	4	Each	Steel End Sections 15"
58100200	249.5	Sq. Yd.	Waterproofing Membrane System
58300100	662	Foot	Portland Cement Mortar Fairing Course
+63000001	75	Foot	Steel Plate Beam Guardrail, Type A, 6 Foot Posts
+63100075	4	Each	Traffic Barrier Terminal, Type 5A
+63100167	4	Each	Traffic Barrier Terminal, Type 1 (Special) Tangent
63200310	317	Foot	Guardrail Removal
66600105	8	Each	Furnishing and Erecting Right of Way Markers
66700205	1	Each	Permanent Survey Markers, Type I
67100100	1	L. Sum	Mobilization
+78200410	8	Each	Guardrail Markers, Type A
+78201000	4	Each	Terminal Marker - Direct Applied
*X2020410	1,340	Cu. Yd	Earth Excavation (Special)
*X2070302	200	Ton	Porous Granular Embankment, Special
*X2501000	0.76	Acre	Seeding, Class 2 (Special)
*X2810210	747	Ton	Stone Riprap, Class A5 (Special)
*X6650200	351	Foot	Woven Wire Fence (Special)
*X7010216	1	L. Sum	Traffic Control and Protection, (Special)
*Z0005400	273	Ton	Breaker-Run Crushed Stone
*Z0022800	437	Foot	Fence Removal

*See B.L.R. 11310 in the contract documents for Special Provisions.

+Specialty Items

FILE = S:\AS\puct\1128006\bridge Drawings\1128006_SummaryofQuantities.dgn



DESIGNED - MICHAEL WAGNER	REVISED -
CHECKED - BRIAN CONVERSE	REVISED -
DRAWN - RON ALLEN	REVISED -
CHECKED - BRIAN CONVERSE	REVISED -

MERCER COUNTY
F.A.S. 217 (C.H. 6) OVER MAIDS RUN
STATION 20+05

SUMMARY OF QUANTITIES
STRUCTURE NO. 066-3031

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
217	05-00096-00-BR	MERCER	21	2
WHA* 1128006		CONTRACT NO. 89432		
ILLINOIS FED. AID PROJECT BRS-02171021				